

**ENGINEERING INVESTIGATIONS  
AT  
INACTIVE HAZARDOUS WASTE SITES  
IN THE  
STATE OF NEW YORK  
PHASE I - PRELIMINARY INVESTIGATION  
FINAL REPORT  
ROYAL CARTING SERVICE SITE**

**CONTRACT NO. D000452  
NYSDEC SITE NO. 314011**

**Submitted To:  
Division of Solid Waste  
New York State  
Department of Environmental Conservation  
50 Wolf Road  
Albany, New York 12233-0001**

**Submitted By:  
Woodward-Clyde Consultants, Inc.  
1250 Broadway, 15th Floor  
New York, New York 10001**

**September 26, 1984**

**82C4548**

355686



1250 Broadway, 15th Floor  
New York, New York 10001  
212-926-2878 (NY/NJ)  
212-594-2118 (Direct)  
Telex 133-541

## Woodward-Clyde Consultants, Inc.

September 26, 1984  
82C4548

New York State Department of Environmental Conservation  
Division of Solid Waste  
Room 209  
50 Wolf Road  
Albany, New York 12233

Attention: Mr. Norman H. Nosenchuck  
Director

Subject: Engineering Investigations at Inactive Hazardous Waste Sites in the  
State of New York  
Phase I - Preliminary Investigation  
Royal Carting Service  
NYSDEC No. 314011  
EPA No. NYD002426757

Dear Sir:

This report presents the results of our Preliminary Investigation of the Royal Carting Service site in Dutchess County, New York. This preliminary investigation fulfills the requirements of Phase I of our Contract No. D000452 to perform engineering investigations at 40 inactive hazardous waste sites in the State of New York. Phase II involves field investigation services at the sites.

The objective of Phase I was to:

- o collect and review data
- o perform a site reconnaissance
- o prepare a draft Hazard Ranking System (HRS) and Documentation
- o develop a specific site work plan for Phase II
- o develop Phase II site investigation costs
- o identify known responsible parties
- o prepare a summary report

Consulting Engineers, Geologists  
and Environmental Scientists

Offices in Other Principal Cities



September 26, 1984  
82C4548  
Page 2

This report contains six sections. Section 1.0 includes a description of the site. Section 2.0 presents the preliminary HRS work sheets, the HRS documentation records, and EPA site assessment forms (2070-12 and 2070-13). Section 3.0 provides a brief summary of the history of site activities. Section 4.0 includes a discussion of existing site data. Section 5.0 provides an assessment of the data adequacy identifying major data gaps. Lastly, Section 6.0 presents the recommended Phase II Site Investigation Work Plan and costs. Sampling and analysis plans and the health and safety plans are not included. These are to be supplied by NYSDEC.

The Royal Carting Service site was originally used as a disposal facility for various forms of mixed municipal and industrial wastes. From 1950 to 1962, the site accepted several hundred 35- and 55-gallon drums and cans of waste chemicals which were subsequently found to be non-hazardous. These drums were buried in a shallow pit onsite and later removed to a NYSDEC-approved disposal area.

The remote site is located in a rural area of East Fishkill. A tributary to Sprout Creek lies about 100 feet to the north. Freshwater wetlands occur within several hundred feet of the site. Griffins Tavern, listed on the State and National Registers of Historic Places, lies within several hundred feet of the access road to the site. All Angel Bog, a State-designated Significant Habitat, occurs approximately 2700 feet to the southwest.

The Royal Carting Service site is reportedly owned by Emile Panichi, Rt. 82, Hopewell Junction, New York.

September 26, 1984  
82C4548  
Page 3

The HRS scores developed for the Royal Carting Service site are as follows:

$S_M = 0.0$  ( $S_{gw} = 0.0$   $S_{sw} = 0.0$   $S_a = 0.0$ )  
 $S_{FE} = N/A$   
 $S_{DC} = 0.0$

In scoring the site, Ground Water, Surface Water and Direct Contact route scores were all set at zero due to incomplete factor data. A total of ten factors were scrutinized using incomplete data. Much of the data inadequacies are due to the fact that it is not known what, if any, hazardous wastes have been disposed of onsite.

The proposed work plan for Phase II activities is specifically designed to address the data gaps identified. We have proposed a limited geophysical survey, the installation of three monitoring wells, two test pits, and limited surface water, sediment and soil sampling. A detailed description of the work plan and costs is provided in Section 6.0. The total estimated cost for Phase II investigations at the Royal Carting Service site is \$27,510.

If there are any questions or comments concerning the work plan or any other portion of the Phase I report, please do not hesitate to contact us.

Very truly yours,



Donald R. Ganser,  
Project Manager

DRG:jc  
enclosure  
C716/134

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 SITE DESCRIPTION	1-1
2.0 U.S. ENVIRONMENTAL PROTECTION AGENCY DOCUMENTATION	2-1
2.1 Preliminary HRS Work Sheets	2-2
2.2 Documentation Records For HRS	2-10
2.3 EPA Form 2070-12	2-24
2.4 EPA Form 2070-13	2-29
3.0 SITE HISTORY	3-1
4.0 SITE DATA	4-1
4.1 Site Area Surface Features	4-1
4.2 Site Hydrogeology	4-1
4.2.1 Ground Water Occurrence	4-1
4.2.2 Ground Water Quality	4-2
4.3 Past Sampling and Analysis	4-3
5.0 DATA ADEQUACY	5-1
6.0 WORK PLAN	6-1
6.1 Objectives	6-1
6.2 Field Investigation Plan	6-1
6.2.1 Geophysical Studies	6-1
6.2.2 Test Pits	6-2
6.2.3 Monitoring Wells	6-2
6.2.3.1 Installation	6-2
6.2.3.2 Water Elevations	6-3
6.2.3.3 Aquifer Testing	6-4
6.2.4 Sampling and Analysis Plan	6-4
6.2.4.1 General Plan	6-4
6.2.4.2 Sampling Parameters	6-4
6.2.4.3 Sampling Locations	6-4
6.3 Health and Safety Plan	6-5
6.4 Cost Estimate	6-5

LIST OF TABLES

---

<u>Table</u>		<u>Page</u>
6-1	PROPOSED CHEMICAL ANALYSES AT THE ROYAL CARTING SERVICE SITE	6-6
6-2	GEOPHYSICAL STUDIES COSTS	6-7
6-3	DRILLING/WELL INSTALLATION COSTS	6-8
6-4	SAMPLING AND ANALYSIS COSTS	6-9
6-5	REPORT PREPARATION COSTS	6-10
6-6	PROJECT MANAGEMENT COSTS	6-11

LIST OF FIGURES

---

Figure

- 1 SITE LOCATION MAP - ROYAL CARTING SERVICE SITE
- 2 LOCATION PLAN FOR PROPOSED PHASE II INVESTIGATION

APPENDICES

---

Appendix

- A REFERENCES
- B PERTINENT INFORMATION
- C UPDATED NEW YORK STATE REGISTRY FORM



1.0

SITE DESCRIPTION

---

The Royal Carting Service site is located one-mile southwest of the intersection of Route 82 and Hopewell-Wappingers Road, and 0.2 miles northeast of All Angels Road and Route 82, on the north side of Route 82 in the Town of East Fishkill (Figure 1). The site was originally used as a disposal facility for miscellaneous waste streams. Today, it is inactive and is utilized for storage of empty dumpsters.

At the time of the WCC Site Survey in April of 1983, miscellaneous trash was observed strewn about the property. The pit where waste drums had been excavated had been backfilled. Several rusty 55-gallon drums, which appeared to be empty, were also observed. A large area of standing water was noted at the back (north) end of the site.

2.0

U.S. ENVIRONMENTAL PROTECTION AGENCY DOCUMENTATION

---

This section includes documentation records and work sheets required to develop Hazard Ranking System (HRS) scores. In addition, two EPA forms regarding site inspection and preliminary assessment have been completed and are included as required.

Documents included in this section are:

1. Preliminary Hazard Ranking System (HRS) Work Sheets
2. Documentation Records for HRS
3. EPA Form 2070-12 (Preliminary Assessment)
4. EPA Form 2070-13 (Site Inspection Report)

All forms were prepared as completely as possible using information available from county, state, and federal agency files. Unfortunately, available information on the site was generally sparse. The interview with Emile Panichi, current owner of the site, conducted during the WCC Site Survey proved to be one of the most useful data sources. The Dutchess County Department of Health (DCDH) also provided limited site specific data.

All information provided in the Documentation Records for HRS are referenced, and copies of pertinent information are included in Appendix B. Analytical results are also included in Appendix B.

2.1 Preliminary HRS Work Sheets

**Facility Name:** Royal Carting Service  
**Location:** Route 82, Hopewell Junction, Dutchess Co. NY  
**KPA Region:** II  
**Person(s) in Charge of the Facility:** Emile Panichi, Owner  
Route 82  
Hopewell Junction, NY 12533  
**Name of Reviewer:** C. Mancini, WCC **Date:** 6 Sept. 83

**General Description of the Facility:**

(For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

From 1950-1962 hundreds of 35 and 55 gallon drums containing non-hazardous waste chemicals from the Texaco Research Center were stored at the site. The drums have been removed, but it is unknown what, if

any, additional wastes are buried in the site vicinity. Data for  $S_{gw}$ ,  $S_{sw}$  &  $S_{DC}$  were inadequate for complete HRS Scoring of the site.

**Scores:**  $S_M = 0.0$  ( $S_{gw} = 0.0$   $S_{sw} = 0.0$   $S_a = 0.0$ )  
 $S_{FE} = N/A$   
 $S_{DC} = 0.0$

GROUND WATER ROUTE WORK SHEET						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Release	<u>0</u> 45	1	0	45	3.1	
If observed release is given a score of 45, proceed to line <b>4</b> . If observed release is given a score of 0, proceed to line <b>2</b> .						
<b>2</b> Route Characteristics					3.2	
Depth to Aquifer of Concern	0 1 2 <u>3</u>	2	6	6		
Net Precipitation	0 1 2 <u>3</u>	1	3	3		
Permeability of the Unsaturated Zone	0 1 2 <u>3</u>	1	3	3		
Physical State	<u>0</u> 1 2 3	1	0	3		
Total Route Characteristics Score			12	15		
<b>3</b> Containment	0 <u>1</u> 2 3	1	1	3	3.3	
<b>4</b> Waste Characteristics					3.4	
Toxicity/Persistence	<u>0</u> 3 6 9 12 15 18	1	0	18		
Hazardous Waste Quantity	<u>0</u> 1 2 3 4 5 6 7 8	1	0	8		
Total Waste Characteristics Score			0	26		
<b>5</b> Targets					3.5	
Ground Water Use	0 1 <u>2</u> 3	3	6	9		
Distance to Nearest Well/Population Served	0 4 8 8 10 12 16 18 20 24 30 32 35 <u>40</u>	1	40	40		
Total Targets Score			46	49		
<b>6</b> If line <b>1</b> is 45, multiply <b>1</b> x <b>4</b> x <b>5</b> If line <b>1</b> is 0, multiply <b>2</b> x <b>3</b> x <b>4</b> x <b>5</b>			0	57.330		
<b>7</b> Divide line <b>6</b> by 57.330 and multiply by 100 $S_{gw} = 0.0^*$						

\* Users Manual, p7 - If data are lacking for more than one factor in connection with the evaluation of a route score, that score is set at 0.

SURFACE WATER ROUTE WORK SHEET						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Release	(0) 45	1	0	45	4.1	
If observed release is given a value of 45, proceed to line <b>4</b> . If observed release is given a value of 0, proceed to line <b>2</b> .						
<b>2</b> Route Characteristics					4.2	
Facility Slope and Intervening Terrain	0 1 (2) 3	1	2	3		
1-yr. 24-hr. Rainfall	0 1 (2) 3	1	2	3		
Distance to Nearest Surface Water	0 1 2 (3)	2	6	6		
Physical State	0 1 2 (3)	1	3	3		
Total Route Characteristics Score			13	15		
<b>3</b> Containment	0 (1) 2 3	1	1	3	4.3	
<b>4</b> Waste Characteristics					4.4	
Toxicity/Persistence	(0) 3 6 9 12 15 18	1	0	18		
Hazardous Waste Quantity	(0) 1 2 3 4 5 6 7 8	1	0	8		
Total Waste Characteristics Score			0	26		
<b>5</b> Targets					4.5	
Surface Water Use	(0) 1 2 3	3	0	9		
Distance to a Sensitive Environment	0 1 (2) 3	2	4	8		
Population Served/Distance to Water Intake Downstream	(0) 4 8 8 10 12 16 18 20 24 30 32 35 40	1	0	40		
Total Targets Score			4	55		
<b>6</b> If line <b>1</b> is 45, multiply <b>1</b> x <b>4</b> x <b>5</b> If line <b>1</b> is 0, multiply <b>2</b> x <b>3</b> x <b>4</b> x <b>5</b>			0	64.350		
<b>7</b> Divide line <b>6</b> by 64.350 and multiply by 100 $S_{sw} = 0.0^*$						

\*Users Manual, p7. If data are lacking for more than one factor in connection with the evaluation of a route score, that score is set at zero.

AIR ROUTE WORK SHEET						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Release ..	(0) 45	1	0	45	5.1	
Date and Location:						
Sampling Protocol:						
If line <b>1</b> is 0, the S = 0. Enter on line <b>5</b> . If line <b>1</b> is 45, then proceed to line <b>2</b> .						
<b>2</b> Waste Characteristics					5.2	
Reactivity and Incompatibility	0 1 2 3	1		3		
Toxicity	0 1 2 3	3		9		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8		
Total Waste Characteristics Score				20		
<b>3</b> Targets					5.3	
Population Within 4-Mile Radius	{ 0 9 12 15 18 / 21 24 27 30	1		30		
Distance to Sensitive Environment	0 1 2 3	2		6		
Land Use	0 1 2 3	1		3		
Total Targets Score				39		
<b>4</b> Multiply <b>1</b> x <b>2</b> x <b>3</b>			0	35,100		
<b>5</b> Divide line <b>4</b> by 35,100 and multiply by 100 $S_a = 0.0$						

	s	s <sup>2</sup>
Groundwater Route Score (S <sub>gw</sub> )	0	
Surface Water Route Score (S <sub>sw</sub> )	0	
Air Route Score (S <sub>a</sub> )	0	
$s_{gw}^2 + s_{sw}^2 + s_a^2$		
$\sqrt{s_{gw}^2 + s_{sw}^2 + s_a^2}$		
$\sqrt{s_{gw}^2 + s_{sw}^2 + s_a^2} / 1.73$		S <sub>M</sub> = 0

WORKSHEET FOR COMPUTING S<sub>M</sub>



N/A

FIRE AND EXPLOSION WORK SHEET													
Rating Factor	Assigned Value (Circle One)								Multi- plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Containment	1	3							1		3	7.1	
<b>2</b> Waste Characteristics												7.2	
Direct Evidence	0	1	2	3					1		3		
Ignitability	0	1	2	3					1		3		
Reactivity	0	1	2	3					1		3		
Incompatibility	0	1	2	3					1		3		
Hazardous Waste Quantity	0	1	2	3	4	5	6	7	8	1	8		
Total Waste Characteristics Score												20	
<b>3</b> Targets												7.3	
Distance to Nearest Population	0	1	2	3	4	5			1		5		
Distance to Nearest Building	0	1	2	3					1		3		
Distance to Sensitive Environment	0	1	2	3					1		3		
Land Use	0	1	2	3					1		3		
Population Within 2-Mile Radius	0	1	2	3	4	5			1		5		
Buildings Within 2-Mile Radius	0	1	2	3	4	5			1		5		
Total Targets Score												24	
<b>4</b> Multiply <b>1</b> x <b>2</b> x <b>3</b>												1,440	
<b>5</b> Divide line <b>5</b> by 1,440 and multiply by 100    SFE = N/A													

DIRECT CONTACT WORK SHEET						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Incident	<u>0</u> 45	1	0	45	8.1	
If line <b>1</b> is 45, proceed to line <b>4</b> If line <b>1</b> is 0, proceed to line <b>2</b>						
<b>2</b> Accessibility	0 1 2 <u>3</u>	1	3	3	8.2	
<b>3</b> Containment	0 <u>19</u>	1	15	15	8.3	
<b>4</b> Waste Characteristics Toxicity	0 <u>1</u> 2 3	5	5	15	8.4	
<b>5</b> Targets					8.5	
Population Within a 1-Mile Radius	0 1 2 3 <u>4</u> 5	4	16	20		
Distance to a Critical Habitat	0 1 <u>2</u> 3	4	8	12		
Total Targets Score			24	32		
<b>6</b> If line <b>1</b> is 45, multiply <b>1</b> x <b>4</b> x <b>5</b> If line <b>1</b> is 0, multiply <b>2</b> x <b>3</b> x <b>4</b> x <b>5</b>				21,600		
<b>7</b> Divide line <b>6</b> by 21,600 and multiply by 100    SOC = <u>0</u> <sup>*</sup>						

\* Users Manual, p7 - If data are lacking for more than one factor in connection with the evaluation of a route score, that score is set at 0.

2.2 Documentation Records For HRS

**DOCUMENTATION RECORDS  
FOR HAZARD RANKING SYSTEM**

**INSTRUCTIONS:** The purpose of these records is to provide a convenient way to prepare an auditable record of the data and documentation used to apply the Hazard Ranking System to a given facility. As briefly as possible summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference that will make the document used for a given data point easier to find. Include the location of the document and consider appending a copy of the relevant page(s) for ease in review.

**FACILITY NAME:** Royal Carting Service

**LOCATION:** Route 82, Hopewell Junction, Dutchess County, New York

GROUND WATER ROUTE

1. OBSERVED RELEASE

Contaminants detected (5 maximum):

None.

Rationale for attributing the contaminants to the facility:

N/A.

\* \* \*

2. ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

1. Surficial stratified deposits of sand and gravel.
2. Stockbridge limestone (bedrock aquifer).  
(Simmons, Grossman & Heath, 1961).

Depth(s) from the ground surface to the highest seasonal level of the saturated zone (water table(s)) of the aquifer of concern:

1. Surficial sand and gravel - 18 to 20 feet.
2. Stockbridge limestone - approximately 50 feet.  
(Simmons, Grossman & Heath, 1961).

Depth from the ground surface to the lowest point of waste disposal/storage:

Unknown.

**Net Precipitation**

**Mean annual or seasonal precipitation (list months for seasonal):**

46 inches (User's Manual).

**Mean annual lake or seasonal evaporation (list months for seasonal):**

29 inches (User's Manual).

**Net precipitation (subtract the above figures):**

17 inches.

**Permeability of Unsaturated Zone**

**Soil type in unsaturated zone:**

Hoosic gravelly loam (USDA, 1939; WCC Site Survey, 1983).

**Permeability associated with soil type:**

Greater than  $10^{-3}$  cm/sec (User's Manual).

**Physical State**

**Physical state of substances at time of disposal (or at present time for generated gases):**

Unknown.

**3. CONTAINMENT**

**Containment**

**Method(s) of waste or leachate containment evaluated:**

Unknown.

**Method with highest score:**

N/A (User's Manual).

**4. WASTE CHARACTERISTICS**

**Toxicity and Persistence**

**Compound(s) evaluated:**

Unknown.

**Compound with highest score:**

N/A.

**Hazardous Waste Quantity**

**Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):**

Unknown.

**Basis of estimating and/or computing waste quantity:**

N/A.

## 5. TARGETS

### Ground Water Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Private potable water supply (DCDH, 1983).

### Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

Rt. 82, owner's potable water (WCC Site Survey, 1983).

Distance to above well or building:

Approximately 750 feet (WCC Site Survey, 1983).

### Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

Unknown, probably all private wells (DCDH, 1983).

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

Unknown.

Total population served by ground water within a 3-mile radius:

More than 10,000 (Donnelly Marketing, 1982; DCDH, 1983).



## **SURFACE WATER ROUTE**

### **1. OBSERVED RELEASE**

**Contaminants detected in surface water at the facility or downhill from it (5 maximum):**

None.

**Rationale for attributing the contaminants to the facility:**

N/A.

### **2. ROUTE CHARACTERISTICS**

#### **Facility Slope and Intervening Terrain**

**Average slope of facility in percent:**

3% (WCC Site Survey, 1983).

**Name/description of nearest downslope surface water:**

Tributary to Sprout Creek (WCC Site Survey, 1983; USGS, 1981).

**Average slope of terrain between facility and above-cited surface water body in percent:**

5 to 8% (WCC Site Survey, 1983).

**Is the facility located either totally or partially in surface water?**

Yes, partially (WCC Site Survey, 1983; USGS, 1981; NYSDEC, 1980b).

Is the facility completely surrounded by areas of higher elevation?

No (WCC Site Survey, 1983; USGS, 1981).

1-Year 24-Hour Rainfall in Inches

2.9 inches (User's Manual).

Distance to Nearest Downslope Surface Water

Approximately 100 feet (WCC Site Survey, 1983).

Physical State of Waste

Unknown.

\* \* \*

**3. CONTAINMENT**

Containment

Method(s) of waste or leachate containment evaluated:

Unknown.

Method with highest score:

N/A.

#### 4. WASTE CHARACTERISTICS

##### Toxicity and Persistence

Compound(s) evaluated

N/A.

Compound with highest score:

N/A.

##### Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

Unknown.

Basis of estimating and/or computing waste quantity:

N/A.

\* \* \*

#### 5. TARGETS

##### Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

Possibly light recreational.

**Is there tidal influence?**

**No.**

**Distance to a Sensitive Environment**

**Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:**

**N/A.**

**Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:**

**Approximately 700 feet to state-designated wetlands (NYSDEC, Division of Fish and Wildlife, 1975).**

**Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:**

**All Angel Bog, a NYS-designated Significant Habitat is located approximately 2500 feet SW of site (NYSDEC, Division of Fish and Wildlife, 1983).**

**Population Served by Surface Water**

**Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:**

**None (DCDH, 1983).**

**Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre):**

N/A.

**Total population served:**

N/A.

**Name/description of nearest of above water bodies:**

N/A.

**Distance to above-cited intakes, measured in stream miles:**

N/A.

AIR ROUTE

1. OBSERVED RELEASE

Contaminants detected:

No evidence.

Date and location of detection of contaminants:

N/A.

Methods used to detect the contaminants:

N/a.

Rationale for attributing the contaminants to the site:

N/A.

\* \* \*

2. WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

Unknown.

Most incompatible pair of compounds:

N/A.

Toxicity

Most toxic compound:

N/A.

Hazardous Waste Quantity

Total quantity of hazardous waste:

Unknown.

Basis of estimating and/or computing waste quantity:

N/A.

\* \* \*

**3. TARGETS**

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

<u>0 to 4 mi</u>	<u>0 to 1 mi</u>	<u>0 to 1/2 mi</u>	<u>0 to 1/4 mi</u>
37,610	3,911	535	-
(Donnelly Marketing, 1982).			

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

N/A.

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

Approximately 700 feet to NYS-designated freshwater wetlands (NYSDEC, Division of Fish and Wildlife, 1975).

**Distance to critical habitat of an endangered species, if 1 mile or less:**

All Angel Bog, a NYS-designated Significant Habitat is located approximately 2500 feet southwest of site (NYSDEC, Division of Fish and Wildlife, 1983).

**Land Use**

**Distance to commercial/industrial area, if 1 mile or less:**

None observed (WCC Site Survey, 1983).

**Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:**

None (USGS, 1981).

**Distance to residential area, if 2 miles or less:**

Approximately 400 feet (WCC Site Survey, 1983).

**Distance to agricultural land in production within past 5 years, if 1 mile or less:**

None (NYS Department of Agriculture and Markets, 1983; WCC Site Survey, 1983).

**Distance to prime agricultural land in production within past 5 years, if 2 miles or less:**

None (NYS Department of Agriculture and Markets, 1983).

**Is a historic or landmark site (National Register of Historical Places and National Natural Landmarks) within the view of the site?**

Griffin's Tavern may be visible from the access road. This site is on the State and National Registers of Historic Places (NYS Parks and Recreation, Division for Historic Preservation, 1983).



2.3 EPA Form 2070-12  
(Preliminary Assessment)



POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT  
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NY

NYD 002 426757

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site)

Royal Carting Service

02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER

Route 82

03 CITY

Hopewell Junction, E. Fishkill

04 STATE

NY

05 ZIP CODE

12524

06 COUNTY

Dutchess

07 COUNTY CODE

027

08 CONG DIST

09 COORDINATES LATITUDE

41 34 05.0

LONGITUDE

073 50 50.0

10 DIRECTIONS TO SITE (Starting from nearest public road)

One mile south west of the intersection of Route 82 and Hopewell-Wappingers Road, and 2/10 of a mile northeast of All Angels Hill Road and Route 82 on the north side of Route 82 in the Town of East Fishkill.

III. RESPONSIBLE PARTIES

01 OWNER (If known)

Emile Panichi

02 STREET (Business, mailing, residential)

Rt. 82

03 CITY

Hopewell Junction

04 STATE

NY

05 ZIP CODE

12533

06 TELEPHONE NUMBER

(914) 896-6000

07 OPERATOR (If known and different from owner)

Same.

08 STREET (Business, mailing, residential)

09 CITY

10 STATE

11 ZIP CODE

12 TELEPHONE NUMBER

( )

13 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE

☐ B. FEDERAL:

(Agency name)

☐ C. STATE

☐ D. COUNTY

☐ E. MUNICIPAL

☐ F. OTHER:

(Specify)

☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)

☐ A. RCRA 3001 DATE RECEIVED:

MONTH DAY YEAR

☐ B. UNCONTROLLED WASTE SITE (CERCLA 103 c) DATE RECEIVED:

MONTH DAY YEAR

☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION

☒ YES  
☐ NO

DATE 04/26/83  
MONTH DAY YEAR

BY (Check all that apply)

☐ A. EPA

☐ B. EPA CONTRACTOR

☐ C. STATE

☒ D. OTHER CONTRACTOR

☐ E. LOCAL HEALTH OFFICIAL

☐ F. OTHER:

CONTRACTOR NAME(S): Woodward Clyde Consultants, Inc.

02 SITE STATUS (Check one)

☐ A. ACTIVE

☒ B. INACTIVE

☐ C. UNKNOWN

03 YEARS OF OPERATION

1950 1962

BEGINNING YEAR

ENDING YEAR

☐ UNKNOWN

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Several hundred drums of non-hazardous materials have already been removed. It is not known what if any additional wastes have been disposed of at the site.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

Proximity to wetlands and surface waters, rapidly permeable soils and depth to ground water about 18' would present potential hazards if any wastes have been disposed of.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents)

☐ A. HIGH

(Inspection required promptly)

☒ B. MEDIUM

(Inspection required)

☐ C. LOW

(Inspect on time available basis)

☐ D. NONE

(No further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT

02 OF (Agency/Organization)

03 TELEPHONE NUMBER

04 PERSON RESPONSIBLE FOR ASSESSMENT

05 AGENCY

06 ORGANIZATION


Woodward Clyde Consultants, Inc.

07 TELEPHONE NUMBER

212 926-3878  
(201) 785-0700

08 DATE

09/01/83  
MONTH DAY YEAR



(NYSDEC Files; USGS Hopewell Junction, NY Quadrangle, 7.5 min. topographic map, 1981)



POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE NY 02 SITE NUMBER CCR 11-22

NYD000426757

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

Proximity to wetlands, rapidly permeable soils, 18' depth to ground water

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

located approximately 100' from tributary to Sprout Creek.

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

No information available (N/A)

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 AREA POTENTIALLY AFFECTED: \_\_\_\_\_ (Acres) 04 NARRATIVE DESCRIPTION

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 WORKERS POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A



POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NY

002,0125

NYD 002406757

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

N/A

01 ☐ K. DAMAGE TO FAUNA  
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

N/A

01 ☒ L. CONTAMINATION OF FOOD CHAIN  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☒ POTENTIAL

☐ ALLEGED

Proximity to wetlands

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES  
(Spills/runoff/standing liquids/leaking drums)

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

N/A

01 ☐ N. DAMAGE TO OFFSITE PROPERTY  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

N/A

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

N/A

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

N/A

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

N/A

III. TOTAL POPULATION POTENTIALLY AFFECTED: 3911 within 1 mile

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

(WCC Site Survey, 1983 ; Donnlley Marketing, 1982)

2.4 EPA Form 2070-13  
(Site Inspection Report)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

D1 STATE NY D2 SITE NUMBER

NYD 002 426 757

II. SITE NAME AND LOCATION

D1 SITE NAME (Legal, common, or descriptive name of site)

Royal Carting Service

D2 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER

Route 82

D3 CITY

Hopewell Junction, E. Fishkill

D4 STATE

NY

D5 ZIP CODE

12524

D6 COUNTY

Dutchess

D7 COUNTY CODE

027

D8 CONG DIST

D9 COORDINATES

LATITUDE

41 34 05.0

LONGITUDE

073 50 50.0

10 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE

☐ B. FEDERAL

☐ C. STATE

☐ D. COUNTY

☐ E. MUNICIPAL

☐ G. UNKNOWN

III. INSPECTION INFORMATION

D1 DATE OF INSPECTION

04/26/83  
MONTH DAY YEAR

D2 SITE STATUS

☐ ACTIVE

☒ INACTIVE

D3 YEARS OF OPERATION

1950

1962

UNKNOWN

BEGINNING YEAR

ENDING YEAR

D4 AGENCY PERFORMING INSPECTION (Check all that apply)

☐ A. EPA

☐ B. EPA CONTRACTOR

☐ C. MUNICIPAL

☐ D. MUNICIPAL CONTRACTOR

☐ E. STATE

☒ F. STATE CONTRACTOR

Woodward Clyde Consult.  
Inc.

☐ G. OTHER

(Specify)

D5 CHIEF INSPECTOR

M.A. Khoury

D6 TITLE

Ass. Project Engineer

D7 ORGANIZATION

Woodward Clyde Consultants

D8 TELEPHONE NO.

(201) 785-0700

D9 OTHER INSPECTORS

10 TITLE

11 ORGANIZATION

12 TELEPHONE NO.

13 SITE REPRESENTATIVES INTERVIEWED

Emile Panichi

14 TITLE

Owner

15 ADDRESS

Rt. 82, Hopewell Junction, NY

16 TELEPHONE NO.

(914) 896-6000

17 ACCESS GAINED BY

(Check one)

☒ PERMISSION

☐ WARRANT

18 TIME OF INSPECTION

1330

19 WEATHER CONDITIONS

Cloudy ; 60°F

IV. INFORMATION AVAILABLE FROM

D1 CONTACT

Emile Panichi

D2 OF (Agency/Organization)

Owner, Royal Carting Service

D3 TELEPHONE NO.

(914) 896-6000

D4 PERSON RESPONSIBLE FOR SITE INSPECTION FORM

Donald R. Ganzer

D5 AGENCY

D6 ORGANIZATION

Woodward Clyde Consultants Inc.

D7 TELEPHONE NO.

(212) 926-2878  
(201) 785-0700

D8 DATE

09/01/83  
MONTH DAY YEAR

**POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 2 - WASTE INFORMATION**

## IDENTIFICATION

01 STATE	02 SITE NUMBER
----------	----------------

NY 0000000000  
NV D002426757

## B. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

<p>01 PHYSICAL STATES (Check all that apply)</p> <p><input type="checkbox"/> A. SOLID                      <input type="checkbox"/> E. SLURRY</p> <p><input type="checkbox"/> B. POWDER, FINES        <input type="checkbox"/> F. LIQUID</p> <p><input type="checkbox"/> C. SLUDGE                  <input type="checkbox"/> G. GAS</p> <p><input type="checkbox"/> D. OTHER <u>Unknown</u></p> <p>(Specify)</p>	<p>02 WASTE QUANTITY AT SITE (Numerical or waste quantities must be independent)</p> <p>TONS _____</p> <p>CUBIC YARDS <u>Unknown</u></p> <p>NO. OF DRUMS _____</p>	<p>03 WASTE CHARACTERISTICS (Check all that apply)</p> <table border="0"> <tr> <td><input type="checkbox"/> A. TOXIC</td> <td><input type="checkbox"/> E. SOLUBLE</td> <td><input type="checkbox"/> I. HIGHLY VOLATILE</td> </tr> <tr> <td><input type="checkbox"/> B. CORROSIVE</td> <td><input type="checkbox"/> F. INFECTIOUS</td> <td><input type="checkbox"/> J. EXPLOSIVE</td> </tr> <tr> <td><input type="checkbox"/> C. RADIOACTIVE</td> <td><input type="checkbox"/> G. FLAMMABLE</td> <td><input type="checkbox"/> K. REACTIVE</td> </tr> <tr> <td><input type="checkbox"/> D. PERSISTENT</td> <td><input type="checkbox"/> H. IRRITABLE</td> <td><input type="checkbox"/> L. INCOMPATIBLE</td> </tr> <tr> <td></td> <td></td> <td><input type="checkbox"/> M. NOT APPLICABLE</td> </tr> </table>	<input type="checkbox"/> A. TOXIC	<input type="checkbox"/> E. SOLUBLE	<input type="checkbox"/> I. HIGHLY VOLATILE	<input type="checkbox"/> B. CORROSIVE	<input type="checkbox"/> F. INFECTIOUS	<input type="checkbox"/> J. EXPLOSIVE	<input type="checkbox"/> C. RADIOACTIVE	<input type="checkbox"/> G. FLAMMABLE	<input type="checkbox"/> K. REACTIVE	<input type="checkbox"/> D. PERSISTENT	<input type="checkbox"/> H. IRRITABLE	<input type="checkbox"/> L. INCOMPATIBLE			<input type="checkbox"/> M. NOT APPLICABLE
<input type="checkbox"/> A. TOXIC	<input type="checkbox"/> E. SOLUBLE	<input type="checkbox"/> I. HIGHLY VOLATILE															
<input type="checkbox"/> B. CORROSIVE	<input type="checkbox"/> F. INFECTIOUS	<input type="checkbox"/> J. EXPLOSIVE															
<input type="checkbox"/> C. RADIOACTIVE	<input type="checkbox"/> G. FLAMMABLE	<input type="checkbox"/> K. REACTIVE															
<input type="checkbox"/> D. PERSISTENT	<input type="checkbox"/> H. IRRITABLE	<input type="checkbox"/> L. INCOMPATIBLE															
		<input type="checkbox"/> M. NOT APPLICABLE															

### III. WASTE TYPE

None known

III. WASTE TYPE		01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
CATEGORY	SUBSTANCE NAME			
SLU	SLUDGE			
OLW	OILY WASTE			
SOL	SOLVENTS			
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

## IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

[illegible]

### V. FEEDSTOCKS (See Appendix for CAS Numbers)

V. FEEDSTOCKS (See Appendix for CAS Numbers)					
CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

**VL SOURCES OF INFORMATION** (Cite specific references, e.g., state files, sample analysis reports)

## NYSDEC Files





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE: NY 02 SITE NUMBER: 000010125  
NYD002426757

2. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

Proximity to wetlands, rapidly permeable soils, 18' depth to ground water.

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

located approximately 100' from tributary to Sprout Creek.

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

No information available (N/A)

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 AREA POTENTIALLY AFFECTED: \_\_\_\_\_ (Acres) 04 NARRATIVE DESCRIPTION

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 WORKERS POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

N/A



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
NY	2000.1.1.1.3
NYD002486757	

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 <input type="checkbox"/> J. DAMAGE TO FLORA	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			
N/A			

01 <input type="checkbox"/> K. DAMAGE TO FAUNA	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION (include name(s) of species)			
N/A			

01 <input checked="" type="checkbox"/> L. CONTAMINATION OF FOOD CHAIN	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input checked="" type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			
Proximity to wetlands			

01 <input type="checkbox"/> M. UNSTABLE CONTAINMENT OF WASTES (Spills/Runoff/Leaking drums)	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			
03 POPULATION POTENTIALLY AFFECTED: _____			
N/A			

01 <input type="checkbox"/> N. DAMAGE TO OFFSITE PROPERTY	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			
N/A			

01 <input type="checkbox"/> O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			
N/A			

01 <input type="checkbox"/> P. ILLEGAL/UNAUTHORIZED DUMPING	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			
N/A			

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS			
N/A			

III. TOTAL POPULATION POTENTIALLY AFFECTED: 3911 within 1 mile

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analyses, reports)

(NYSD&C, 1975; USDA 1939; USGS 1981; WCC Site Survey 1983)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION  
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE NY 02 SITE NUMBER 660010125  
NYD002426757

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPOC PLAN				
<input checked="" type="checkbox"/> G. STATE (Specify)	3A-003	10-5-82	10-22-82	Waste Transporter Permit
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input checked="" type="checkbox"/> None	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> A. INCINERATION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input checked="" type="checkbox"/> H. OPEN DUMP	Unknown		<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> I. OTHER (Specify)			<input type="checkbox"/> H. OTHER (Specify)	

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one) Unknown  
☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

Original wastes were contained in rusty, leaking drums. Containment of any additional wastes which may have been disposed of on-site is unknown

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☒ YES ☐ NO

02 COMMENTS

Site is surrounded by a complete barrier, with controlled entry and is posted. Once on the site, waste area is easily accessible.

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

(NYSDEC, 1982a; WCC Site Survey 1983)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I IDENTIFICATION

01 STATE NY 02 SITE NUMBER 00010123  
N/D002426757

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY  
(Check as applicable)

SURFACE WELL  
COMMUNITY A ☐ B ☐  
NON-COMMUNITY C ☐ D ☒

02 STATUS

ENDANGERED A ☐ B ☐ C ☐  
D ☐ E ☐ F ☒

03 DISTANCE TO SITE

A \_\_\_\_\_ (mi)  
B 400' (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☐ A. ONLY SOURCE FOR DRINKING

☒ B. DRINKING

(Other sources available)

COMMERCIAL, INDUSTRIAL IRRIGATION  
(No other water sources available)

☐ C. COMMERCIAL, INDUSTRIAL IRRIGATION  
(Listed other sources available)

☐ D. NOT USED, UNUSABLE

02 POPULATION SERVED BY GROUND WATER more than 10,000 within 5 mi

03 DISTANCE TO NEAREST DRINKING WATER WELL 400' (mi)

04 DEPTH TO GROUNDWATER

18 (m)

05 DIRECTION OF GROUNDWATER FLOW

southwest

06 DEPTH TO AQUIFER  
OF CONCERN

18 (m)

07 POTENTIAL YIELD  
OF AQUIFER

unknown (gpd)

08 SOLE SOURCE AQUIFER

☐ YES ☒ NO

09 DESCRIPTION OF WELLS (including storage, depth, and location relative to population and buildings)

Well owned by E. Panichi, owner - tested twice yearly.

10 RECHARGE AREA

☒ YES  
☐ NO

COMMENTS

11 DISCHARGE AREA

☐ YES  
☐ NO

COMMENTS

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☐ A. RESERVOIR, RECREATION  
DRINKING WATER SOURCE

☐ B. IRRIGATION, ECONOMICALLY  
IMPORTANT RESOURCES

☐ C. COMMERCIAL, INDUSTRIAL

☒ D. NOT CURRENTLY USED

Possibly light recreation

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:

tributary to Sprout Creek

AFFECTED

DISTANCE TO SITE

100'

(mi)

(mi)

(mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE

A. 3911  
NO. OF PERSONS

TWO (2) MILES OF SITE

B. 12,386  
NO. OF PERSONS

THREE (3) MILES OF SITE

C. 37610  
NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

Several hundred feet.  
(mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

Approximately 3000

04 DISTANCE TO NEAREST OFF-SITE BUILDING

400' (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

Site is located in remote, rural area.



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NY 000002426757

NYD002426757

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A.  $10^{-6} - 10^{-8}$  cm/sec ☐ B.  $10^{-4} - 10^{-6}$  cm/sec ☐ C.  $10^{-4} - 10^{-3}$  cm/sec ☒ D. GREATER THAN  $10^{-3}$  cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE (Less than  $10^{-6}$  cm/sec) ☐ B. RELATIVELY IMPERMEABLE ( $10^{-4} - 10^{-6}$  cm/sec) ☒ C. RELATIVELY PERMEABLE ( $10^{-2} - 10^{-4}$  cm/sec) ☐ D. VERY PERMEABLE (Greater than  $10^{-2}$  cm/sec)

03 DEPTH TO BEDROCK

≈ 50 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

Unknown (ft)

05 SOIL pH

Unknown

06 NET PRECIPITATION

17 (in)

07 ONE YEAR 24 HOUR RAINFALL

2.9 (in)

08 SLOPE

3 %

DIRECTION OF SITE SLOPE

west

TERRAIN AVERAGE SLOPE

5-8 %

09 FLOOD POTENTIAL

SITE IS IN \_\_\_\_\_ YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

A. \_\_\_\_\_ (mi)

OTHER

B. 700' (mi)

12 DISTANCE TO CRITICAL HABITAT (minimum distance)

Significant 2500' (mi)

ENDANGERED SPECIES: \_\_\_\_\_

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

a. None observed (mi)

RESIDENTIAL AREAS, NATIONAL/STATE PARKS,  
FORESTS, OR WILDLIFE RESERVES

b. 400' (mi)

AGRICULTURAL LANDS  
PRIME AG LAND

c. None (mi)

AG LAND

d. None (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Site is in a relatively low lying area in the vicinity of Sprout Creek. Approximate elevation is 230' above MSL. On-site topography is variable but in the range of 3%. There is a general downward slope toward the back (northwest) of the site.

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

(WCC Site Survey 1983; USGS 1981; Users Manual; NYSDDEC, 1983; Donnelly Marketing 1982; Simmons, Grossman and Heath, 1961; NYSDA&M 1983)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE NY 02 SITE NUMBER 64001000

NYD002426757

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE	<u>3</u>	<u>Camo Laboratories</u>	<u>1-27-82</u>
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>Woodward-Clyde Consultants</u> <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>Woodward-Clyde Consultants</u>

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

(Camo Labs, 1982 ; WCC Site Survey)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NY

0000000000

NYD002426757

II. CURRENT OWNER(S)

01 NAME Emile Panichi			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.) Rt. 82			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY Hopewell Junction			06 STATE NY			07 ZIP CODE 12533			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		

III. PREVIOUS OWNER(S) (List most recent first)

01 NAME Unknown			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		
01 NAME			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		
01 NAME			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis reports)

(wcc Site Survey 1983)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE NY 02 SITE NO. 15  
NYP002426757

II. CURRENT OPERATOR (Provide if different from owner)

01 NAME None		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					

OPERATOR'S PARENT COMPANY (if applicable)

III. PREVIOUS OPERATOR(S) (List most recent first, provide only if different from owner)

01 NAME Unknown		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

PREVIOUS OPERATORS' PARENT COMPANIES (if applicable)

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analyses, reports)

(WCC Site Survey, 1983)





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE #  
NY 10125  
NYD002426757

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME Texaco Research Center	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY Glenham	06 STATE NY	07 ZIP CODE	05 CITY 06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

(DCDH 1982d)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NY 050010125

NYD002426757

II. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ D. SPILLED MATERIAL REMOVED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ E. CONTAMINATED SOIL REMOVED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ F. WASTE REPACKAGED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☒ G. WASTE DISPOSED ELSEWHERE  
04 DESCRIPTION

02 DATE

03 AGENCY

10-82 DC DH  
Buried wastes were excavated and disposed  
at the Doughkeepsie landfill. Wastes were non-hazardous

01 ☒ H. ON SITE BURIAL  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ I. IN SITU CHEMICAL TREATMENT  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ J. IN SITU BIOLOGICAL TREATMENT  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ K. IN SITU PHYSICAL TREATMENT  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ L. ENCAPSULATION  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ M. EMERGENCY WASTE TREATMENT  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ N. CUTOFF WALLS  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ O. EMERGENCY DRAIN/SURFACE WATER DIVERSION  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ P. CUTOFF TRENCHES/SUMP  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Q. SUBSURFACE CUTOFF WALL  
04 DESCRIPTION

02 DATE

03 AGENCY



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NY

NYD022426757

II. PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ S. CAPPING/COVERING  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ T. BULK TANKAGE REPAIRED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ U. GROUT CURTAIN CONSTRUCTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ V. BOTTOM SEALED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ W. GAS CONTROL  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ X. FIRE CONTROL  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Y. LEACHATE TREATMENT  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Z. AREA EVACUATED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 1. ACCESS TO SITE RESTRICTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 2. POPULATION RELOCATED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 3. OTHER REMEDIAL ACTIVITIES  
04 DESCRIPTION

02 DATE

03 AGENCY

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

(DCDH 1982d)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

D1 STATE NY D2 SITE NO. 0123  
NYD0002426757

ENFORCEMENT INFORMATION

D1 PAST REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO

DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

State entered into a consent Order with owner in November of 1982 to rectify the situation.

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

(NYS DEC 1982b)

3.0

SITE HISTORY

---

The Royal Carting Service site was originally used as a disposal facility for various forms of mixed municipal and industrial wastes (NYSDEC, 1979). From 1950 to 1962, the site accepted several hundred 35- and 55-gallon drums and cans of waste chemicals generated by the Texaco Research Center in Glenham, New York (Pagones, Cross and Van Tuyl, 1981; NYSDEC, 1982c). The site was purchased by Emile Panichi, the current owner, in 1971 (WCC Site Survey, 1983).

In August of 1979, NYSDEC performed a site investigation of "Reported Hazardous Waste Sites" (NYSDEC, 1979). Another inspection was performed in April of 1980 (NYSDEC, 1980a). During these inspections, the investigators observed "mixed municipal waste and trash" and hundreds of full barrels, drums and cans with unidentified contents. In November of 1981, the DCDH in conjunction with the NYSDEC, collected three waste samples from the site (NYSDEC, 1981). All three samples were found to consist of non-hazardous waste materials (Camo Labs, 1982; Poughkeepsie Journal, 1982).

In June of 1982, Mr. Panichi had the materials buried in a shallow pit on the property (DCDH, 1982c). In October of that year, the waste drums were excavated and disposed of at the F.I.C.A. Landfill in the Town of Poughkeepsie (DCDH, 1982d).

4.0

SITE DATA

---

**4.1 Site Area Surface Features**

Royal Carting Service is located on a remote site in a rural area of East Fishkill. The ground surface demonstrates a rolling topography, with an approximate site elevation of 230 feet and a variable slope to the northwest in the 3% range (USGS, 1981). A tributary to Sprout Creek lies approximately 100 feet from the northern site boundary. Freshwater wetlands occur within several hundred feet of the site (NYSDEC, Division of Fish and Wildlife, 1975) and low-lying areas of standing water occur within the site boundaries (WCC Site Survey, 1983). The latter is not considered to be designated state wetlands as it does not meet the minimum 12.4-acre minimum size criteria (NYSDEC, 1980b). Griffins Tavern, listed on State and National Registers of Historic Places, lies within several hundred feet of the access road to the site on Route 82 (NYSP&R, 1983). All Angel Bog, a State-designated Significant Habitat, occurs approximately 2700 feet southwest on Route 82 (NYSDEC, 1983).

Land use in the area is somewhat rural and residential (WCC Site Survey, 1983). The nearest dwelling is located approximately 400 feet from the site and is owned by Emile Panichi, the owner of Royal Carting Service. It is estimated that approximately 30 dwellings occur within 1/4 mile of the site, and more than 200 within one mile. No commercial, industrial, or agricultural areas were observed in the site vicinity during the WCC Site Survey (WCC, 1983).

## 4.2 Site Hydrogeology

**4.2.1 Ground Water Occurrence.** Ground water in the site area occurs in both consolidated bedrock and in unconsolidated deposits. In general, the most productive aquifers in the area are sand and gravel glacial outwash deposits associated with local valleys. One such sand and gravel deposit underlies the Royal Carting Service site to a depth of approximately 50 feet (Simmons, Grossman and Heath, 1961). Recharge to this aquifer is primarily through precipitation, but may also occur from hydraulically-linked surface water bodies. These unconsolidated sand and gravel deposits are utilized extensively in Dutchess County and generally yield adequate quantities of water for domestic, farm and small commercial needs. The reported depth to ground water in an overburden well in the immediate vicinity of the site is 18 feet (Simmons, Grossman and Heath, 1961).

The Orodovician and Cambrian Stockbridge limestone formation is the bedrock unit underlying most of the valley areas of Dutchess County, including the Royal Carting Service site. The Stockbridge limestone is the most productive bedrock aquifer in the county, with yields averaging about 22 gpm and ranging up to 220 gpm (Simmons, Grossman and Heath, 1961). Significant quantities of ground water are typically associated with zones of fracturing or faulting. Hence, the most productive bedrock wells are in valley areas where fracturing is most abundant.

Recharge of bedrock aquifers in the area is generally by infiltration of precipitation or by percolation through overlying unconsolidated deposits. Bedrock overlain by permeable sand and gravel deposits, as it is in the site area, is typically more productive than bedrock overlain by less permeable till or clay.

**4.2.2 Ground Water Quality.** Analyses of ground water from unconsolidated deposits overlying limestone in Dutchess County indicate water of moderate hardness and dissolved solids content. Likewise, iron, sulfate and chloride concentrations are moderate to low in some areas.

Ground water analyses from consolidated deposits of the Stockbridge limestone demonstrate similar trends for iron, but sulphate concentrations tend to be somewhat higher and locally high chloride levels also occur. Total hardness for ground water from this formation demonstrates similar median values but a much wider range indicating greater local variability (Simmons, Grossman and Heath, 1961).

**4.2.3 Ground Water Use.** Ground water is widely used in Dutchess County, but most individual supplies are small. Rural homes, farms and some suburban sections of Dutchess County which are not served by public supply utilize individually-owned, private wells.

Being located in a generally rural area of the county, residences in the vicinity of the site are supplied by private wells. Approximately 1000 households occur within one-mile of the Royal Carting Service site (Donnelly Marketing, 1982) which most likely utilize private wells. Several miles downgradient, a small private supplier, Brinkerhoft Company, has a shallow gravel well which serves a school and housing development. There are no public supply wells in the immediate vicinity of the site (DCDH, 1983).

The closest private well is located approximately 400 feet from the site. This potable well is owned and utilized by Emile Panichi, owner of the Royal Carting Service site. The well is tested twice each year and, based on interview with Mr. Panichi, has shown no signs of contamination (WCC Site Survey, 1983).

**4.3 Past Sampling and Analysis**

As far as is known, no ground water analyses have been performed at the site.

As indicated above, water quality analyses have been performed twice a year on the potable water well owned by Emile Panichi and located several hundred feet from the site. These analyses have demonstrated no contamination at this point (WCC Site Survey, 1983).



5.0

DATA ADEQUACY

---

Existing available data were sparse, and generally inadequate for HRS Scoring of the Royal Carting Service site. Much of the data utilized in this effort was gained through the WCC Site Survey and interview with Emile Panichi, the owner of the site. The Dutchess County Department of Health files also provided some limited information on the site. The HRS User's Manual specifies, that if data are lacking for more than one factor in connection with the evaluation of a route score, that score is set at zero. In scoring the Royal Carting Service site, Ground Water, Surface Water and Direct Contact route scores were all set at zero due to incomplete factor data. A total of ten factors were scrutinized using incomplete data (signified with squares on the work sheets).

Most of the data inadequacies are due to the fact that it is not known what, if any, hazardous wastes have been disposed of onsite. Those wastes which were originally discovered were found to be non-hazardous and removed. Hence, major data gaps include waste characteristics such as quantity, state, toxicity and persistence of potential hazardous wastes which may have been disposed of onsite. Data on the method of containment of these potential wastes is also needed.

6.0  
WORK PLAN

---

6.1 Objectives

The objective of this work plan is to collect essential field information required to adequately prepare a final HRS Score and develop conceptual remedial designs and costs. There is generally only minimal existing information on the Royal Carting Service site. Hence, the work plan will address questions primarily concerning ground and surface water flow and quality, soils, stream sediments and the occurrence and characteristics of any additional wastes which may be found at the site.

6.2 Field Investigation Plan

6.2.1 Geophysical Studies. As part of the onsite field investigation to characterize the hydrologic regime, a geophysical survey utilizing the terrain conductivity technique will be performed at the site. This technique has been utilized successfully in locating subsurface plumes of many different substances. Measurements will be taken at various locations in the site vicinity to determine expected ranges of background or upgradient conductivity (locations will be governed by the amount of open space between trees). Measurements will be taken across and around the site to identify the presence and direction of movement of any existing plumes of contaminated ground water, and to identify anomalous conductivity distributions that may indicate buried metallic objects such as drums or other containers.

It is anticipated that it will require a two-person team two days to perform the conductivity survey, with readings taken at an exploration depth of 25 feet

at each measurement station. The data will be plotted on maps and contoured. These contour maps will provide the basis for defining the exact number and location of additional ground water monitoring wells.

**6.2.2 Test Pits.** Test pits will be excavated by backhoe at various locations around the site as shown in Figure 2. The main purpose of these pits will be to provide soil samples for chemical testing, thus allowing a delineation of the possible locations of additional buried wastes or of contaminated soils. The pits will be approximately 10 to 15 feet deep. One will be located in the old waste drum burial pit, and one near the northern dumpster storage area. A Priority Pollutant Analysis will be performed on one composite soil sample. Additional sampling for metals and volatile organics will be conducted if deemed necessary.

### **6.2.3 Monitoring Wells**

**6.2.3.1 Installation.** Monitoring wells will be installed to provide data pertinent to water chemistry near the top of the ground water table and characterization of stratigraphy and the ground water regime at the site. It is recommended that three monitoring wells be installed, at the approximate locations shown in Figure 2. Finalized well locations will be determined after geophysical data has been plotted and reduced.

Well MW-1 will be installed at a presumed upgradient location, just northeast of the Royal Carting Service building. This well will provide representative samples of the ground water flowing into the area.

Well MW-2 will be situated west of the old waste drum pit in a presumed downgradient location. Well MW-3 will be located in the northwest portion of the site, also in a presumed downgradient location. These two approximate locations will provide the greatest opportunity for interception of any potential contaminant plumes which may emanate from the site.

All monitoring wells will be installed so as to sample the upper 10 feet of ground water. It is assumed that the ground water table will be within 25 feet of the ground surface and into unconsolidated sediments of sand and gravel. In the site vicinity, the thickness of this water bearing unit is approximately 50 feet (Simmons, Grossman and Heath, 1961).

Borings will be advanced through overburden by 6-inch I.D. hollow stem augers or driven casing with continuous split spoon sampling through the upper 15 feet of soil, and at 5-foot intervals below 15 feet. Soil samples will be classified in the field by a hydrogeologist. Selected samples will be submitted to WCC's geotechnical laboratory for grain analysis and Atterberg limits if required. To maximize information on any volatile or organic contaminants, headspace analysis will be conducted on soil samples, using a portable gas chromatograph. These data will be used to evaluate relative concentrations of organic contaminants in various stratigraphic horizons.

Slotted 3-inch I.D. PVC well screen will be installed over 10-foot intervals in each well, with a riser of flush joint, threaded, 3-inch I.D. PVC pipe. In low-lying areas, risers will extend at least 3 feet above the ground surface to prevent contamination by surface water flooding. A gravel pack will be completed to approximately 2 feet above the top of the screen, where a one-foot bentonite seal will be installed. To further assure that water samples will be representative of the screened interval, the remaining annular space will be grouted, and a protective steel casing will be installed. After installation, all wells will be developed by pumping, to remove any fine grained material.

**6.2.3.2 Water Elevations.** Ground water depths will be measured at the time of well development and again at the time of pumping. Relative well elevations will be surveyed by WCC personnel. Water elevations will be plotted and used to develop contours of the ground water table at the site. Based on this map, the direction(s) of ground water flow will be calculated. Flow and

gradient data will be fundamental input in quantifying site conditions and will be assessed together with plume geometries inferred from geophysical survey data.

**6.2.3.3 Aquifer Testing.** "Slug"-type permeability tests will be conducted in each newly installed well to evaluate the permeability of materials spanning the screened interval. The method is a rapid means by which the in-situ permeability in the immediate vicinity of a monitoring well can be approximated. The test does not involve pumping of potentially contaminated water and results generally suffice for ground water flow analysis.

**6.2.4 Sampling and Analysis Plan**

**6.2.4.1 General Plan.** Sampling and analysis plan to be supplied by NYSDEC.

**6.2.4.2 Sampling Parameters.** Previous sampling at the site is non-existent. Therefore, sampling parameters should cover a wide variety of contaminants. Samples will be collected from ground and surface waters, stream sediments and soils. Sample types and chemical parameters are summarized in Table 6-1. At a minimum, one Priority Pollutant Analysis will be performed on one composite soil sample and one ground water sample.

**6.2.4.3 Sampling Locations.** One water sample and one soil sample from two of the three proposed ground water monitoring wells will be analyzed for metals and volatile organics. Results of each pair of analyses will be compared to evaluate any downward migration of contaminants through soil. Ground water analyses will be evaluated in terms of other hydrogeologic data to evaluate the presence, distribution, and migration directions of any ground water contaminant plumes.

Surface water samples will be collected at two locations, one upstream and one downstream, in the site vicinity, with sediment samples collected at the same locations. The upstream sample will provide information concerning the

quality of surface water flowing into the site vicinity. The downstream sample will provide information concerning the quality of surface waters leaving the site.

**6.3 Health and Safety Plan**

Health and safety plan to be supplied by NYSDEC.

**6.4 Cost Estimate**

Costs for Phase II work were developed based on assumptions, rates, and charges described in WCC's cost proposal submitted to NYSDEC on 29 October 1982. Costs have been grouped by task, and estimates are presented in Tables 6-2, 6-3, 6-4, 6-5, and 6-6. The estimated costs may require adjustment as a result of the requirements of the sampling and analysis plan or health and safety plan to be supplied by NYSDEC. The total estimated cost for Phase II investigations at the Royal Carting Service site is \$27,510.

Table 6-1. PROPOSED CHEMICAL ANALYSES AT THE ROYAL CARTING SITE.

<u>Sample Type</u>	<u>ANALYSES</u>		<u>Remarks</u>
	<u>Metals</u>	<u>Volatile Organics</u>	
Ground Water*	X	X	One sample from one well if deemed necessary.
Soil*	X	X	One sample from one test pit if deemed necessary.
Surface Water	X	X	One sample each from one upstream and one downstream location.
Stream Sediment	X	X	One sample each from one upstream and one downstream location.

\*At a minimum, one Priority Pollutant Analysis will be performed on one composite soil sample and one ground water sample.

TABLE 6-2. GEOPHYSICAL STUDIES COSTS.

		<u>Estimated Cost</u>	<u>Total Estimated Cost</u>
1. Direct Material			
a. Purchased Parts			
b. Subcontract Items			
c. Other			
2. Material Overhead			
	<u>Estimated Hours</u>	<u>Rate/ Hour</u>	
3. Direct Labor			
Senior Staff Engineer/ Geologist/Scientist	48	12.62	606
	<b>Total Direct Labor</b>		<b>\$ 606</b>
	<u>O H Rate</u>	<u>X Base</u>	
4. Labor Overhead	120%	606	727
	<b>Total Labor Overhead</b>		<b>\$ 727</b>
5. Special Testing			
6. Special Equipment-Terrain Conductivity Equipment (EM-34)			<b>\$ 400</b>
7. Travel			
a. Transportation		67	
	<b>Total Travel</b>		<b>\$ 67</b>
8. Consultants			
	<b>Total Consultants</b>		<b>-</b>
9. Other Direct Costs			
10.	<b>Total Direct Costs and Overhead</b>		<b>\$1,800</b>
11. General and Administrative Expense (rate 15% of Cost Element No's. 1, 3, 4, 7, 9)			<b>\$ 210</b>
12. Royalties			
13.		<b>Sub-Total</b>	<b>\$2,010</b>
14. Fee		181	
15.	<b>Total Estimated Cost</b>		<b>\$2,191</b>



TABLE 6-3. DRILLING/WELL INSTALLATION COSTS.

		<u>Estimated Cost</u>	<u>Total Estimated Cost</u>
1. Direct Material			
a. Purchased Parts			
b. Subcontract Items		\$ 7,405	
c. Other			
	<b>Total Direct Material</b>		<b>\$ 7,405</b>
2. Material Overhead			
	<u>Estimated Hours</u>	<u>Rate/ Hour</u>	
3. Direct Labor			
Senior Staff Engineer/ Geologist/Scientist	65	12.62	820
	<b>Total Direct Labor</b>		<b>\$ 820</b>
	<u>O H Rate</u>	<u>X Base</u>	
4. Labor Overhead	120%	820	984
	<b>Total Labor Overhead</b>		<b>\$ 984</b>
5. Special Testing			
6. Special Equipment			
Century Organic Vapor Analyzer		250	
Photovac 10A10 Gas Chromatograph		450	
	<b>Total Special Equipment</b>		<b>\$ 700</b>
7. Travel			
a. Transportation		34	
b. Subsistence		300	
	<b>Total Travel</b>		<b>\$ 334</b>
8. Consultants			
	<b>Total Consultants</b>		<b>-</b>
9. Other Direct Costs			
10.	<b>Total Direct Costs and Overhead</b>		<b>\$10,243</b>
11. General and Administrative Expense (rate 15% of Cost Element No's. 1, 3, 4, 7, 9)			<b>\$ 1,432</b>
12. Royalties			
13.	<b>Sub-Total</b>		<b>\$11,675</b>
14. Fee		1,051	
15.	<b>Total Estimated Cost</b>		<b>\$12,726</b>

TABLE 6-4. SAMPLING AND ANALYSIS COSTS.


		<u>Estimated Cost</u>	<u>Total Estimated Cost</u>
1. Direct Material			
a. Purchased Parts			
b. Subcontract Items		\$4,950	
c. Other			
	<b>Total Direct Material</b>		<b>\$4,950</b>
2. Material Overhead			
	<u>Estimated Hours</u>	<u>Rate/ Hour</u>	
3. Direct Labor			
Staff Engineer/ Geologist/Scientist	16	11.54	185
	<b>Total Direct Labor</b>		<b>\$ 185</b>
	<u>O H Rate</u>	<u>X Base</u>	
4. Labor Overhead	120%	185	222
	<b>Total Labor Overhead</b>		<b>\$ 222</b>
5. Special Testing			
Laboratory Permeability Test			\$ 190
Grain Size Analyses			\$ 870
Atterberg Limits			\$ 165
6. Special Equipment - Pumps, Bailers			\$ 100
7. Travel			
a. Transportation		34	
b. Subsistence		60	
	<b>Total Travel</b>		<b>\$ 94</b>
8. Consultants			
	<b>Total Consultants</b>		<b>-</b>
9. Other Direct Costs			
Sample Shipment		300	\$ 300
10.	<b>Total Direct Costs and Overhead</b>		<b>\$ 7,076</b>
11. General and Administrative Expense (rate 15% of Cost Element No's. 1, 3, 4, 7, 9)			\$ 863
12. Royalties			
13.	<b>Sub-Total</b>		<b>\$ 7,939</b>
14. Fee		715	
15.	<b>Total Estimated Cost</b>		<b>\$ 8,654</b>

TABLE 6-5. REPORT PREPARATION COSTS.

			<u>Estimated Cost</u>	<u>Total Estimated Cost</u>
1. Direct Material				
a. Purchased Parts				
b. Subcontract Items				
c. Other				
2. Material Overhead				
	<u>Estimated Hours</u>	<u>Rate/ Hour</u>		
3. Direct Labor				
Senior Staff Engineer/ Geologist/Scientist	33	12.62	416	
Draftsperson	10	10.24	102	
Typist	4	8.44	34	
		<b>Total Direct Labor</b>		<b>\$ 552</b>
	<u>O H Rate</u>	<u>X Base</u>		
4. Labor Overhead	120%	552	662	
		<b>Total Labor Overhead</b>		<b>\$ 662</b>
5. Special Testing				
6. Special Equipment				
7. Travel				
a. Transportation				
b. Subsistence				
8. Consultants				
		<b>Total Consultants</b>		<b>-</b>
9. Other Direct Costs				<b>\$ 150</b>
10.		<b>Total Direct Costs and Overhead</b>		<b>\$ 1,364</b>
11. General and Administrative Expense (rate 15% of Cost Element No's. 1, 3, 3, 7, 9)				<b>\$ 205</b>
12. Royalties				
13.		<b>Sub-Total</b>		<b>\$ 1,569</b>
14. Fee		141		
15.		<b>Total Estimated Cost</b>		<b>\$ 1,710</b>

TABLE 6-6. PROJECT MANAGEMENT COSTS.

			<u>Estimated Cost</u>	<u>Total Estimated Cost</u>
1. Direct Material				
a. Purchased Parts				
b. Subcontract Items				
c. Other				
2. Material Overhead				
	<u>Estimated Hours</u>	<u>Rate/ Hour</u>		
3. Direct Labor				
Principal In Charge	2	33.32	67	
Activity Leader	12	20.92	251	
Project Manager	12	20.91	251	
Asst. Prj. Engr/Geol/Sci.	12	14.96	180	
Typist	4	8.44	34	
		<b>Total Direct Labor</b>		<b>\$ 783</b>
	<u>O H Rate</u>	<u>X Base</u>		
4. Labor Overhead	120%	783	940	
		<b>Total Labor Overhead</b>		<b>\$ 940</b>
5. Special Testing				
6. Special Equipment				
7. Travel				
a. Transportation			55	
b. Subsistence				
		<b>Total Travel</b>		<b>\$ 55</b>
8. Consultants				
		<b>Total Consultants</b>		<b>-</b>
9. Other Direct Costs				
10.		<b>Total Direct Costs and Overhead</b>		<b>\$1,778</b>
11. General and Administrative Expense				
(rate 15% of Cost Element No's. 1, 3, 4, 7, 9)				<b>\$ 267</b>
12. Royalties				
13.		<b>Sub-Total</b>		<b>\$2,045</b>
14. Fee		184		
15.		<b>Total Estimated Cost</b>		<b>\$2,229</b>



**NOTE:**


BASE MAP FROM USGS, HOPEWELL JUNCTION, N.Y., QUAD, PHOTO REVISED 1981

**SITE LOCATION MAP  
ROYAL CARTING SERVICE**




**WOODWARD—CLYDE CONSULTANTS, INC.**

CONSULTING ENGINEERS, GEOLOGISTS AND ENVIRONMENTAL SCIENTISTS  
NEW YORK, NEW YORK

DR. BY: DRS	SCALE: 1 IN. = 2000 FT	PROJ. NO.: 82C4548-14
CK'D. BY: CM	DATE: 27 SEPT. 1983	FIG. NO.: 1



# **LEGEND**

-  PROPOSED MONITORING WELL
-  PROPOSED SURFACE WATER SAMPLING
-  PROPOSED TEST PIT LOCATION

## **LOCATION MAP FOR PROPOSED PHASE II INVESTIGATION ROYAL CARTING SERVICE SITE**

**WOODWARD—CLYDE CONSULTANTS, INC.**  
CONSULTING ENGINEERS, GEOLOGISTS AND ENVIRONMENTAL SCIENTISTS  
NEW YORK, NEW YORK

DR. BY: ORS	SCALE: NOT TO SCALE	PROJ. NO.: 82C4548-14
CK'D. BY: CM	DATE: 27 SEPT. 1983	FIG. NO.: 2

**APPENDIX A  
REFERENCES**

---

- CAMO Laboratories, 1982, Analytical report on samples #DEC-1, DEC-2, and DEC-3, Log No.: 81-11-9530, (LOCATION: WCC Files).
- Dutchess County Health Department, 1982a, Memo to File from Donna Sofokles, RE: Royal Carting - Laboratory Analyses of Suspected Hazardous Wastes, dated January 29, 1982, (LOCATION: WCC Files).
- Dutchess County Health Department, 1982b, Memo to Sal Ervolina from David T. Ruff, RE: Royal Carting Co., Town of East Fishkill, dated July 14, 1982, (LOCATION: WCC Files).
- Dutchess County Health Department, 1982c, Memo to Pete Barton from Ellis W. Adams, RE: Royal Carting, T. East Fishkill, dated August 25, 1982, (LOCATION: WCC Files).
- Dutchess County Health Department, 1982d, Letter to NYSDEC, Division of Solid Waste from Jack R. Hill, RE: Limited Waste Transporter Permit for Royal Carting Services Co., dated September 27, 1982, (LOCATION: WCC Files).
- Dutchess County Health Department, 1983, Personal communication with Jack Hill, dated April 21, 1983, (LOCATION: WCC Files).
- NYSDEC, 1975, Freshwater wetlands maps of Dutchess County, Hyde Park Quadrangle, Division of Fish and Wildlife, (LOCATION: NYSDEC/Albany Files).
- NYSDEC, 1979, Hazardous waste site report compiled by Dave Ruff, dated August 14, 1979, (LOCATION: WCC Files).
- NYSDEC, 1980a, Hazardous Wastes Site Report on Royal Carting Site #314011, performed by Jack Doty, April 14, 1980, (LOCATION: WCC Files).
- NYSDEC, 1980b, Memo to Robert Vrana from William E. Steidle, RE: Royal Carting Co., (LOCATION: WCC Files).
- NYSDEC, 1981, Letter to Emile Panichi from Jack Doty, RE: In Place Toxic Site #314011, dated November 16, 1981, (LOCATION: WCC Files).
- NYSDEC, 1982a, NYSDEC Waste Transporter Permit No. 3A-003, issued to Royal Carting Service Co., Inc. October 5, 1982, (LOCATION: WCC Files).
- NYSDEC, 1982b, Letter to Tony Pagones from Laura Zeisel, RE: Royal Carting Company, dated November 12, 1982 (LOCATION: WCC Files).
- NYSDEC, 1982c, Letter to Roy Jacobs, Texaco, Inc., from John Doty, RE: Royal Carting Service In Place Toxic Site #314011, (LOCATION: WCC Files).




- NYSDEC, 1983, Listings and maps of Significant Habitats in Dutchess County, Division of Fish and Wildlife, Significant Habitats Unit, (LOCATION: NYSDEC/Albany Files).
- NYS Parks and Recreation, 1983, Files of Dutchess County Historical Sites Listed on State and Federal Registers, Division for Historic Preservation, (LOCATION: NYSP&R/Albany Files).
- Pagones, Cross and Van Tuyl, P.C., 1981, Letter to John Doty, NYSDEC, from Anthony Pagones, RE: In Place Toxic Site #314011, dated November 18, 1981, (LOCATION: WCC Files).
- Poughkeepsie Journal, 1982, Article entitled "Material in Hopewell found 'non-hazardous'", dated January 31, 1982, (LOCATION: WCC Files).
- Simmons, E.T., I.G. Grossman, and R.C. Heath, 1961, Ground-Water Resources of Dutchess County, New York, NYSDEC, Water Resources Commission, Bulletin C-W-43, Albany, New York, (LOCATION: WCC Files).
- U.S. Department of Agriculture, 1939, Soil Survey, Dutchess County, New York, Series 1939, No. 23, Soil Conservation Service in cooperation with Cornell University Agricultural Experiment Station, (LOCATION: WCC Files).
- U.S. EPA, 1980, Potential Hazardous Waste Site Identification and Preliminary Assessment Form #T2070-2, Royal Carting Service, dated October 30, 1980, (LOCATION: WCC Files).
- U.S. EPA, 1981, Potential Hazardous Waste Site Preliminary Assessment Form #2070, Royal Carting Service, (LOCATION: WCC Files).
- U.S. Fish and Wildlife Service, 1983, National Wildlife Refuges, A Visitor's Guide.
- U.S. Geological Survey, 1981, Hopewell Junction, New York, 7.5-Minute Quadrangle, (LOCATION: WCC Files).
- Woodward-Clyde Consultants, 1983, Site Survey of Royal Carting Service site conducted 21 April 1983 by M.A. Khoury, Assistant Project Engineer, (LOCATION: WCC Files).

**APPENDIX B**  
**PERTINENT INFORMATION**

---

Invoice

(CAMO LABS, 1982)



# CAMO LABORATORIES

A DIVISION OF CAMO POLLUTION CONTROL, INC.

POUGHKEEPSIE AREA FACILITY:  
CAMO LABORATORY  
25 POST ROAD  
HYDE PARK, N.Y. 12538  
(914) 229-8337 or 229-8865

ROCHESTER AREA FACILITY:  
LOZIER/CAMO LABORATORY  
23 NORTH MAIN STREET  
FAIRPORT, N.Y. 14450  
(716) 325-2210  
PLANT OFFICE

January 27, 1982

RECEIVED

Dutchess County Health Department  
22 Market Street  
Poughkeepsie, N.Y. 12601

Attention: Mr. Jack Hill

JUL 22 1982

BUREAU OF  
HAZARDOUS WASTE TECHNOLOGY  
DIVISION OF SOLID WASTE

RE: Analytical Report  
CAMO Log No.: 81-11-9530

Dear Sir:

CAMO Laboratories received three (3) semi-solid samples on November 25, 1981, with a request to determine if these materials were hazardous or not. The results of that investigation are the subject of this report.

If you have any questions, please feel free to call. Thank you.


Sincerely,

CAMO LABORATORIES

*John P. Dullaghan* (JE)

John P. Dullaghan  
Director  
Measurement Services

JPD:el  
Enclosures



# CAMO LABORATORIES

A DIVISION OF CAMO POLLUTION CONTROL, INC.

POUGHKEEPSIE AREA FACILITY:  
CAMO LABORATORY  
25 POST ROAD  
HYDE PARK, N.Y. 12538  
(914) 229-8337 or 229-8865

ROCHESTER AREA FACILITY:  
LOZIER/CAMO LABORATORY  
23 NORTH MAIN STREET  
FAIRPORT, N.Y. 14450  
(716) 425-2210

## ANALYTICAL REPORT

### Hazardous Waste Determination

CAMO Log No.: 81-11-9530

### INTRODUCTION

CAMO Laboratories received three (3) semi-solid samples on November 25, 1981, identified as DEC #1 - polymer, DEC #2 - grease and DEC #3 - solid. The request was to determine if these samples were hazardous with respect to EPA "Hazardous Waste Regulations".

### METHODOLOGY

All three samples were analyzed for ignitability, corrosivity, toxicity, and reactivity, as per EPA "Hazardous Waste and Consolidated Permit Regulations", Federal Register, May 19, 1980.

### RESULTS AND DISCUSSION

All data is presented on Table I. The results indicate that all three (3) samples are non-hazardous materials.

DUTCHESS COUNTY HEALTH DEPARTMENT

Table 1

HAZARDOUS WASTE DETERMINATION

DEC 27 1982

PARAMETER

SAMPLE IDENTIFICATION

DEC #1

DEC #2

DEC #3

EPA Regulations-  
Maximum - Non-  
Hazardous Constit-  
uent Concentrations

IGNITABILITY  
(OF)

276

182

No Flash Point  
up to 210, at  
100°F sample  
foams

Flash Point must  
be <140°F

CORROSIVITY  
(inches/yr)

$1.0 \times 10^{-3}$

$1.3 \times 10^{-3}$

$1.6 \times 10^{-3}$

Corrode steel  
<0.25 inches/yr.

REACTIVITY

Non-Reactive

Non-Reactive

Non-Reactive

Unstable, react  
violently with  
water, generate  
toxic gases, etc.

TOXICITY (EP)  
(mg/l)

Arsenic

0.23

<0.001

<0.001

5.0

Barium

<0.10

<0.10

<0.10

100.0

Cadmium

0.58

<0.003

0.005

1.0

Chrome

2.72

<0.01

<0.01

5.0

Lead

<0.03

<0.03

0.090

5.0

Mercury

<0.001

<0.001

<0.001

0.2

Selenium

<0.001

0.010

0.002

1.0

Silver

<0.006

<0.006

<0.006

5.0

Endrin

<0.0001

<0.0001

<0.0001

0.02

Lindane

<0.001

<0.001

<0.001

0.4

Methoxychlor

<0.001

<0.001

<0.001

10.0

Toxaphene

<0.001

<0.001

<0.001

0.5

2,4-D

<0.05

<0.05

<0.05

10.0

2,4,5-TP

<0.005

<0.005

<0.005

1.0

# CAMO LABORATORIES

A DIVISION OF CAMO POLLUTION CONTROL, INC.

POUGHKEEPSIE AREA FACILITY  
CAMO LABORATORY  
25 POST ROAD  
HYDE PARK, N.Y. 12538  
(914) 229-8337 or 229-8865

ROCHESTER AREA FACILITY  
LOZIER/CAMO LABORATORY  
23 NORTH MAIN STREET  
FAIRPORT, N.Y. 14450  
(716) 425-2210

**BILLED TO:**

Dutchess County Health Department  
22 Market Street  
Poughkeepsie, New York 12601  
  
Attn: Mr. Jack Hill

**SENT TO:**

SAME

LOG NO:	YOUR ORDER NO:	DATE:	INVOICE NO:	TERMS:
81-11-9530	N/A	January 27, 1982	81-11-9530	NET 30 DAYS

**DESCRIPTION**

**TOTAL**

The following charge is for three (3) semi-solid samples received on November 25, 1981, and analyzed for Ignitability, Corrosivity, Reactivity, and Toxicity.

The report was written and signed by Mr. John P. Dullaghan on January 27, 1982.

TOTAL ..... \$1,665.00

PAYMENTS RECEIVED			PLEASE REMIT PAYMENT TO:	PAY LAST AMOUNT IN THIS COLUMN
DATE	CHECK NO.	AMOUNT	<b>CAMO LABORATORIES</b> 25 ALBANY POST ROAD HYDE PARK, NEW YORK 12538 (914) 229-8337 229-8865	

AFTER 30 DAYS, A MONTHLY SERVICE CHARGE OF 1-1/2 % PER MONTH, OR AN ANNUAL PERCENTAGE RATE OF 18 %, WILL BE APPLIED TO UNPAID BALANCES. GOVERNMENTAL AGENCY

(DCDH, 1981)

DUTCHESS COUNTY HEALTH DEPARTMENT

MEMORANDUM

TO: Jack R. Hill, Ellis W. Adams and File  
FROM: Michael E. Takacs  
SUBJECT: Royal Carting, Town of East Fishkill  
DATE: March 25, 1981

On March 24, 1981 a field inspection was conducted at the above site in regards to 55 gallon drums and 5 gallon pails deposited by Texaco 15 to 20 years ago.

The following were present:

Jack Doty of DEC  
Ehmel Panichi-Royal Carting  
William T. Shepherd-Texaco  
Charles A. MacKenzie-Texaco  
Robert Alazagaszi - DEC  
Cecil Johnson-DEC  
Dennis Young-DEC

Visual inspection revealed these drums to have been randomly deposited, many of the pails were open and appeared to contain grease. Texaco has no records pertaining to the contents of the drums, although a solvent type odor was present.

Since the drum contents are unknown, it was determined that sampling of the drums could be hazardous so no samples were collected at this time.

The location of a majority of the drums and pails are along the bank of a tributary of the Sprout Creek which increases the possibility of contaminated runoff during heavy rains.

Removal of these drums and pails to an approved disposal site should be carried out as soon as possible.

MET/pal

(DCDH, 1982a)

DUTCHESS COUNTY HEALTH DEPARTMENT

MEMORANDUM

TO: File  
FROM: Donna Sofokles  
SUBJECT: Royal Carting - Laboratory Analyses of Suspected Hazardous Wastes  
DATE: January 29, 1982

Per telephone conversation with Sherri Lutton, Camo Laboratories:

CAMO received 3 samples for analyses on November 25, 1981. Samples were identified as: DEC #1  
DEC #2  
DEC #3

All three samples were considered non-hazardous material.

Each sample was analyzed for the following parameters:

- Ignitability - All had flash points greater than 140.  
None were in violation of E.P.A. regulations.
- Corrosivity - All were less than E.P.A. violation limits.
- Reactivity - All three samples were non-reactive.
- EP Toxicity - Only materials which showed were on sample #1.  
Some chrome, cadmium, and arsenic. All levels well below E.P.A. regulations limits.
- Herbicides - None found.
- Pesticides - None found.



(DCDH, 1982b)

DUTCHESS COUNTY HEALTH DEPARTMENT

MEMORANDUM

TO: Sal Ervolina, DEC, White Plains  
FROM: David T. Ruff *[Signature]*  
SUBJECT: Royal Carting Co., Town of East Fishkill  
DATE: 7/14/82

*(of Dutchess Co.)*

On July 14, 1982 Ellis Adams conducted a site investigation and spoke with Emil Panichi pertaining to the burial of containers with chemical wastes.

Mr. Adams' report to me indicates that apparently a considerable amount of the containers and wastes were buried on site. They were buried at an approximate depth of 3 to 4 feet. Some containers are protruding through the ground surface. Some of the containers and wastes were reported by Mr. Panichi to have been taken to the F.I.C.A., Fishkill-East Fishkill and Harlem Valley Landfills.

Mr. Adams' report indicates that Mr. Panichi is willing to cooperate on what remedial action may be necessary.

As we agreed, I am referring this matter to you for your review and action. I would appreciate your prompt response and to keep this Department advised on the status. If you wish further assistance or action from this Department, please advise.

dtr/mb

cc: Dr. John R. Scott  
Jack R. Hill  
John F. Lazarony  
File ✓

DUTCHESS COUNTY HEALTH DEPARTMENT

(DCDH, 1982c)

MEMORANDUM

TO: Pete Barton, NYSDEC Conservation Officer  
FROM: Ellis W. Adams, Public Health Sanitarian  
SUBJECT: Royal Carting, T. East Fishkill  
DATE: August 25, 1982

On or about the end of June, Mr. Emil Panichi, owner of Royal Carting, ordered a dozer to dig a trench and bury approximately 150-200 barrels of grease, polymers and related materials in it. The originator of these wastes was the Texaco Research Center, Glenham, NY, some 15-20 years ago. They were buried within 10'-15' of where they were stored all those years. They were buried about 150' to rear (northwest) of the offices for Royal Carting in an area about 100' square, to a depth of 3-4'. A few containers were protruding thru the surface.

This Department is in the process of finding a licensed landfill where this material can be properly deposited. Mr. Panichi has stated he is willing to remove.

We expect removal to take no more than three days, once a site is found for disposal.

The mailing address is as follows:

Mr. Emil Panichi  
c/o Royal Carting Co.  
Route 82  
Hopewell Junction, NY 12533

It is located 1 mile southwest of the intersection of Route 82 and Hopewell-Wappingers Road and 2/10 of a mile northeast of the intersection of All Angels Hill Rd. & Route 82, on the north side of Route 82 in the Town of East Fishkill.

Any questions, do not hesitate to call.

EWA:ds  
cc: file

(DCDH, 1982d)

DUTCHESS COUNTY  
DEPARTMENT OF HEALTH  
22 Market Street  
Poughkeepsie, New York 12601



September 27, 1982

NYS Dept. of Environmental Conservation  
Division of Solid Waste  
Bureau of Hazardous Waste Management  
50 Wolf Road  
Albany, New York 12233

Re: Royal Carting Services Co.  
Limited (One-time) Waste Transporter Permit  
T. East Fishkill

Gentlemen:

Enclosed please find the following data:

- 1) Dutchess County Health Department memorandum to Pete Barton, NYSDEC, with information relative to problem materials.
- 2) 2 copies of 47-19-1, Application for Industrial Waste Collector Registration
- 3) A check in the amount of \$35.00 for three trucks to be used.
- 4) Form SW-14, Industrial Waste Collector Registration Form Continuation.
- 5) Copy of analyses of subject materials performed by CAMO Laboratories. (In DEC File)

Mr. Emil Panichi, owner of Royal Carting Services, estimates it will take approximately two weeks to transport the materials to the approved landfill. Please issue the necessary permit for a two-week period.

If any further information is required, please advise this office immediately at (914)485-9820.

Very truly yours,

*Jack R. Hill*  
Jack R. Hill, Director  
Environmental Health Services

JRH:ds  
enc.  
cc: file

## APPLICATION FOR SEPTIC TANK CLEANER AND INDUSTRIAL WASTE COLLECTOR REGISTRATION

1. NAME OF BUSINESS <b>AL CARTING SERVICE CO. INC.</b>		2. LOCATION WHERE VEHICLES ARE GARAGED <b>Route 82, Hopewell Junction</b>			3. NO. OF VEHICLE <b>3</b>	
4. BUSINESS ADDRESS <b>Route 82</b>		City & State <b>Hopewell Junction, NY</b>		Zip Code <b>12533</b>	Telephone No. <b>896-6000</b>	REGISTRATION NO.
VEHICLE NO.						
VEHICLES	1	2	3	4	5	6
MAKE	<b>Mack</b>	<b>Mack</b>	<b>Mack</b>			
YEAR	<b>1975</b>	<b>1977</b>	<b>1978</b>			
COLOR	<b>Green</b>	<b>Green</b>	<b>Green</b>			
LICENSE PLATE NO.	<b>55609GD</b>	<b>9469MM</b>	<b>2467GO</b>			
STATE OF REGISTRATION	<b>NY</b>	<b>NY</b>	<b>NY</b>			
TYPE (Tank, open, etc.)	<b>Roll-off</b>	<b>Roll-off</b>	<b>Roll-off</b>			
TANK CAPACITY	<b>20 yd.</b>	<b>20 yd.</b>	<b>20 yd.</b>			

NOTE: For additional vehicles and/or information, please attach a supplemental sheet and check here ☐

PHYSICAL AND CHEMICAL CHARACTER OF WASTES HANDLED NOTE: If Industrial Wastes are handled, form SW-14 must also be completed.

**Industrial grease and polymers**

## LOCATION AND MANNER OF DISPOSAL

**Landfill - F.I.C.A. Landfill  
Town of Poughkeepsie**

## PLACE OR COMMUNITIES SERVED

Attach a map or sketch showing the disposal area of receiving station

10. \$25.00 Annual Registration Fee attached ☐ Yes ☐ No

I hereby affirm under penalty of perjury that information provided on this form is true to the best of my knowledge and belief. False statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law.

SIGNATURE OF APPLICANT

12. PRINTED OR TYPED NAME

13. DATE

## STATEMENT OF OWNERS OR OPERATORS OF DISPOSAL AREAS OR RECEIVING STATIONS

Permission is hereby granted to the above named applicant to dump the material stated in this application at site(s) listed below subject to the Rules and Regulations of the Department of Environmental Conservation governing disposal of such material at the designated area.

1. DISPOSAL SITE OR RECEIVING STATION (1)

NAME OF DISPOSAL SITE OR RECEIVING STATION (2)

DATE

DATE

SIGNATURE

DATE

[illegible]

## INDUSTRIAL WASTE COLLECTOR REGISTRATION FORM CONTINUATION

[illegible]

Date 4/21/83

Time 1130

**Affiliation(s)**

**Phone No.****Location(s)****To**

22 Market St.

~~(FROM)~~ Jack Hill

## Dutchess Co. Water

9/4/431-2048

Poughkeepsie, NY

**Recorded**

by T. Campbell

**Woodward-Clyde Consultants**

**SUBJECT:** - Wells w/in Dutchess Co.

**Record (Pertinent Facts and Data):**

\*36 Royal Carting Site - no public wells in vicinity, only private wells

Location: R+ 82

and All Angels Hill  
Road.

Location - changed to  
Huswell Quay

- The site was a transfer point for solid waste (ie - small trucks brought in trash, big trucks took it to a landfill).

- This site has been cleaned up by the county - shouldn't be a problem any more <sup>immediate</sup>

There are no public wells in the area -  
only private wells, but a small private company, Brinkerhoff,  
owns well (whether owned) = 13,000' diameter near  
the Fairhill Creek; serve a school and development

- IBM E. Fishkill Plant wells serve  $\pm 10,000$  people

#35 Jones Excavation - • this was/is a septa sludge dump site that at one point also received industrial sludge

- The Dutchess Co. Water Authority, has analyzed results from the industrial sludge.

- High Park Fair and Water Dist. have supplemental supply wells (500' deep) located near the Maritime Kill south of Crown Elbow Road approx 7,500 ft down slope of the site. Main water supply is from surface water out of Crown Elbow Creek. It <sup>District</sup> serves 4-5,000 people and is  $< 1$  miles from site.

- Two trailer parks (Val Kill Park East and Hidden Brook Estates) have shallow wells within 2000 and 4500 feet of Site. They serve 83 and 33 units, respectively.

1. Haverland, J. 1922 (11) 6

• Harvard Hall  $N.O \approx 50'$  2,000 people

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
REPORTED HAZARDOUS WASTE SITES

(NYSDEC, 1979)

(11)

#5-1

Date August 14, 1979

D.E.C. Region 1

County Dutchess

Site Owner Royal Carting Service

EMIL PAX

Site Name, if any

Location Route 82

East Fishkill, New York

(MAIL) P.O. Box 12533

Site Description-(size, topography, residences, surface water, vegetation, land use, accessibility to people, etc.) Approximately 5 acres. flat, may be wetland. Sparsely vegetated around periphery of site, isolated from public. No residences within 1/4 mile.

Waste Description-(containers, physical character, odors, color, source, etc) Mixed municipal waste and trash. Hundreds of (55 gallon) and cans, many full - contents unidentified. Possibly TE...

Propane EM

Remarks-(names of others who may have knowledge of this site and any additional pertinent information) Inspected 1/30/80. No leachate evident.

Source of information Dave Ruff

Phone 485-9706

Address Dutchess County Health Department

Information Received By Bob Vrana

Phone 485-9707

Title Assistant Public Health Engineer

Is this site included in the list of 520 sites in the In-Place Toxics Task Force Report? Yes ☐ No ☒

If field inspection is made, the site should be described using the Initial Evaluation of Industrial & Hazardous Waste Site Inspection form.



AL CARTING

24-81

FILLED

PALETS

BEL.

BBC

BELS.

FLOW ~~INTERMITTENT~~  
STREAM

← WADS →

COMPACTOR

OFFICE

RT. 82

NO SAMPLES COLLECTED

HAZARDOUS WASTE DISPOSAL SITES REPORT  
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

(N43DEC, 1980a)

Code: B  
 Site Code: 314011  
 Name of Site: Royal Carting Service Region: 3  
 County: Dutchess Town/City: East Fishkill  
 Street Address: Route 82 East Fishkill

## Status of Site Narrative:

Approximately 5 acres, flat; may be wetland. Sparsely vegetated around periphery of site; isolated from public. No residences within  $\frac{1}{2}$  mile.

Mixed municipal waste and trash. Hundreds of barrels, drums, (55 gallon) and cans, many full-contents unidentified.

Type of Site: Open Dump ☒ Treatment Pond(s) ☐ Number of Ponds \_\_\_\_\_  
 Landfill ☐ Lagoon(s) ☐ Number of Lagoons \_\_\_\_\_  
 Structure ☐

Estimated Size 5 Acres

Hazardous Wastes Disposed? Confirmed ☐ Suspected ☒

## \*Type and Quantity of Hazardous Wastes:

TYPE	QUANTITY (Pounds, drums, tons, gallons)
Unidentified drums	Hundreds
_____	_____
_____	_____
_____	_____
_____	_____

\*Use additional sheets if more space is needed.

Name of Current Owner of Site: Royal Carting

Address of Current Owner of Site: \_\_\_\_\_

Time Period Site Was Used for Hazardous Waste Disposal:

19 63+ To

19

Is site Active ☐ Inactive ☒

(Site is inactive if hazardous wastes were disposed of at this site and site was closed prior to August 25, 1979)

Types of Samples: Air ☐ Groundwater ☐ None ☒  
Surface Water ☐ Soil ☐Remedial Action: Proposed ☐ Under Design ☐  
In Progress ☐ Completed ☐

Nature of Action: none

Status of Legal Action: none State ☐ Federal ☐Permits Issued: Federal ☐ Local Government ☐ SPDES ☐  
Solid Waste ☐ Mined Land ☐ Wetlands ☐ Other ☐

## Assessment of Environmental Problems:

Leaches to Sprout Creek. Additional sampling to determine needs to be completed (of the various media) to determine environmental impact.

## Assessment of Health Problems:

None known.

## Persons Completing this Form:

Jack DotyRon TramontanoG. David KnowlesNew York State Department of Environ-  
mental ConservationDate 4/14/80

New York State Department of Health

Date 4/14/80

(NYSD&C, 1980b)

New York State Department of Environmental Conservation

MEMORANDUM

REC'D

OCT 22 1980

DEPT. OF ENVIRONMENTAL CONSERVATION

FROM: Robert Vrana, Dutchess County Health Department  
William E. Steidle, Regulatory Affairs *WES*  
SUBJECT: Royal Carting Co., NYS Route 82, Town of East Fishkill

DATE: October 21, 1980

We are in receipt of your memorandum of October 9, 1980 regarding possible violations of the Freshwater Wetlands Act at the above site.

Prior to your request, this office inspected the Royal Carting property and a proposed subdivision site (Watch Hill Holding #2) located immediately to the east. Based upon our evaluation it was determined that the ponded area located on both properties was considerably less than 12.4 acres in total size and therefore not subject to the Freshwater Wetlands Act.

If appropriate, we suggest that your Department coordinate with our Division of Solid Waste in order to effectuate corrective action at the site.

Thank you for bringing this matter to my attention. Please let me know if you require additional information or assistance.

WES/mem

cc: S. Ervolina (w/incoming)

(NYSDEC, 1981)

202 Mamaroneck Avenue, White Plains, New York 10601

November 16, 1981

Mr. Emil Panichi  
c/o Royal Carting Co.  
Route 82  
Hopewell Junction, New York 12533

Re: In Place Toxic Site #314011

Dear Mr. Panichi:

As we discussed by phone on Friday, November 13th, personnel of the Dutchess County Department of Health and myself shall collect samples for analysis from the above referenced site. This shall be performed under authorization of the NYS Environmental Conservation Law Section 27-1308(3)(4). Split samples will be provided you or your designee, if desired.

I will further advise you of the time of our visit on Monday, November 23rd. If you have any questions regarding this, you may contact Richard Gardineer at this office or Ellis Adams of the Dutchess County Health Department.

Very truly yours,

John Doty  
Principal Engineering  
Technician

JD/vg

cc: Jack Hill/Ellis Adams  
Richard Gardineer  
Site Discovery & Investigation Section

**WASTE TRANSPORTER PERMIT**


Pursuant to 6 NYCRR Part 364

No. of Additional Sheets: 0

NYSDEC PERMIT NUMBER <b>3A-003</b>	EPA TRANSPORTER ID NUMBER	VEHICLE LICENSE NUMBER <b>2467GO</b>	STATE OF NEW YORK <b>New York</b>
<b>THIS IS TO CERTIFY THAT:</b>			
NAME OF PERMITTEE <b>Royal Carting Service Company, Inc.</b>			
STREET ADDRESS <b>Route 82</b>			
CITY <b>Hopewell Junction</b>	COUNTY	STATE <b>NY</b>	ZIP CODE <b>12533</b>
Having complied with the provisions of Environmental Conservation Law Title 3, is hereby authorized to engage in waste transporting within the State of New York in the manner described herein.			
TYPE OF WASTE AND LOCATION OF TREATMENT, STORAGE OR DISPOSAL FACILITY			
<b>industrial grease and polymers</b>		<b>FICA Landfill Poughkeepsie, NY</b>	
CONDITIONS:			
<p>Disposal facility must be in compliance with all Federal, State and local regulations. This permit is valid only for the waste grease and polymers, estimated quantity (150-200 drums), from Royal Carting Property. No other waste may be transported under this permit.</p>			
THIS PERMIT WILL EXPIRE AT MIDNIGHT <b>October 22, 82</b> and is subject to revocation at any time.			
In witness whereof, the Department of Environmental Conservation has caused this permit to be executed on the <b>5</b> day of <b>October</b> <b>82</b>			
By _____ New York State Department of Environmental Conservation			

(NYSDEC, 1982b)

New York State Department of Environmental Conservation  
21 South Putt Corners Road  
New Paltz, New York 12561-1696  
(914) 255-5453



Robert F. Flacke  
Commissioner

NOV 15 1982

November 12, 1982

Tony Pagones  
Pagones & Cross, P.C.  
Route 52  
Hopewell Junction, New York 12533

Re: Royal Carting Company

Dear Mr. Pagones:

Please excuse the delay in responding to you. Enclosed for your reference is the current Part 360 of Title 6 of the Official Compilation of Codes, Rules and Regulations ("6NYCRR") effective March 9, 1982.

As stated previously, the Department is alleging that your client, Royal Carting Company, had a bulldozer dig a trench and bury approximately 150-200 barrels of grease, polymers and related materials at the site located on Route 82 in Hopewell Junction. Part 360.2a of 6NYCRR states that no person shall:

"Initiate construction or modification of a solid waste management facility except in accordance with a valid construction permit issued to such person by the Department pursuant to this part."

The Department believes that the actions taken by your client in June constitute an illegal landfilling, since no permit was obtained nor was one applied for. These actions, therefore, constitute a violation of Part 360.2a of 6NYCRR.

Also, Part 360.8(a)(21) states that the owner/operator of an active/inactive facility either with/without a permit under this part shall...maintain such facility so as to prevent adverse environmental or health impacts such as, but not limited to, contravention of surface or groundwater quality standards, gas migration, odors and vectors. Therefore, the Department requires that the materials buried by your client (barrels and contaminated soil) must be removed to a licensed landfill in order to mitigate any potential hazards. Therefore, the Department is insistant that a Consent Order be entered into in which Respondent would agree to rectify the present situation.

Tony Pagonas  
Page 2  
November 12, 1982

The Department is also willing to modify the Consent Order to include a paragraph that would basically state the following:

By consenting to the form and entry of this Order, Respondent does not admit any violation of the Environmental Conservation Law ("ECL") or the rules and regulations promulgated thereunder. However, Respondent joins with the Department in its desire to resolve this matter amicably and does hereby agree to adhere to the conditions of this Order.

I will look forward to hearing from you by the end of this month in response to this letter. If we do not receive a response by that time, we will assume you are not willing to consent to our offer. Formal legal proceedings will then be instituted by the Department to obtain the necessary remediation and appropriate penalties.

Very truly yours,

Laura Zeisel  
Regional Attorney  
Region 3

By: Abby M. Snyder  
Legal Assistant

LZ:MS:mc  
Enclosure

bcc: T. Washburn/M. Murray/P. Barton w/enc.  
R. Gardineer w/enc.  
File w/enc.  
P.D.K/Chron w/out enc.  
Suspense: Nov. 30, 1982 w/out enc.



(NYSD&C, 1982c)

Tefaco Inc.  
2000 Westchester Ave.  
Harrison, N.Y. 10528

Attn: Roy Jacobs

Re: Royal Carting Service  
In Place Topic Site #314011

Dear Mr. Jacobs,

As I have not received any information from you since our phone conversation last month, I shall reiterate my request.

As mandated by Article 27, Title 13, Section 27-1307 of the Environmental Conservation Law, please submit to me within thirty (30) days, copies of contracts between Tefaco and Royal Carting Service, for the removal and disposal of waste products generated by the Brewster Tefaco Research Center, for the period 1955 through 1965.

If you have any questions regarding submission of this information, you may contact Rich Gardiner or myself at 761-6660.

Very truly yours

cc: J. Hill - D.C.H.D.  
R. Gardiner  
Site Investigation Section  
bcc: P. Keller

John A. Doty  
Regional Topic Substance  
Control Unit

(Pagones, Cross & Van Tuyl, 1981)

**PAGONES, CROSS & VAN TUYL, P.C.**


ATTORNEYS AND COUNSELLORS AT LAW

855 MAIN STREET

P. O. BOX 230

BEACON, NEW YORK 12508

TELEPHONE (914) 831-2900



November 18th, 1981

BRANCH OFFICE:  
ROBERT MARK OFFICE BLDG. No. 2  
ROUTE 52 - P. O. BOX 299  
HOPEWELL JUNCTION, NEW YORK 12588  
TELEPHONE (914) 897-4100

ANTHONY L. PAGONES  
FRANCOIS R. CROSS  
JENNIFER L. VAN TUYL  
JAMES D. PAGONES

New York State Dept. of  
Environmental Conservation  
202 Mamaroneck Avenue  
White Plains, New York 10601

ATTENTION: Mr. John Doty,  
Principal Engineering Technician

RE: In Place Toxic Site #314011

Dear Mr. Doty:

This will acknowledge receipt of your letter of November 16, 1981 relative to the above to my client, Emil Panichi, c/o Royal Carting Co., and to confirm your scheduled visit on November 23rd, 1981.

We want to emphasize at this time that Mr. Panichi and Royal Carting Co. are in no way responsible for the placing of the material in question at the present site. The contents of the drums apparently emanated at the Texaco laboratory in Glenham, New York. The drums were deposited at the present location at some time in the 1960's, at a time that the property was owned by the predecessor in title.

It is to be understood that our consent to your intended visit is not an acknowledgement or admission on our part of any responsibility for said material and its final disposition.

Very truly yours,

PAGONES, CROSS & VAN TUYL, P.C.

  
ANTHONY L. PAGONES

ALP:am

(Poughkeepsie Journal, 1982)

Received  
From  
Family

Received from  
Family

4/26/83

**Poughkeepsie Journal—SD**

**Material in Hopewell  
found 'non-hazardous'**

**HOPEWELL JUNCTION** — The 200 55-gallon drums stored at the Royal Carting site on Route 82 contain non-hazardous materials, according to test results.

The tests were performed for the Dutchess County Department of Health by the Camo Pollution Control laboratory in Hyde Park, which released the results Friday.

Jack Hill, county public health administrator, said that although the material — a solid petroleum product — is not harmful, he would recommend that the drums be removed from the refuse hauler's property.

"They should go to a landfill," said Hill.

The test findings mean the drums and their contents can be dumped in any operating landfill in Dutchess County, Hill said.

The health department had reported earlier that the drums originally came from a Texaco research facility in Glenham, near Beacon.

**Sunday, January 31, 1982**

(USEPA, 1979)



# POTENTIAL HAZARDOUS WASTE SITE IDENTIFICATION AND PRELIMINARY ASSESSMENT

REGION **II** SITE NUMBER (to be assigned by HQ) **NY000010125**

**NOTE:** This form is completed for each potential hazardous waste site to help set priorities for site inspection. The information submitted on this form is based on available records and may be updated on subsequent forms as a result of additional inquiries and on-site inspections.

**GENERAL INSTRUCTIONS:** Complete Sections I and III through X as completely as possible before Section II (Preliminary Assessment). File this form in the Regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

## I. SITE IDENTIFICATION

A. SITE NAME <b>Royal Carting Service</b>		B. STREET (or other identifier) <b>Rte 82</b>	
C. CITY <b>East Fishkill</b>	D. STATE <b>NY</b>	E. ZIP CODE <b>12524</b>	F. COUNTY NAME <b>Dutchess.</b>
G. OWNER/OPERATOR (if known) 1. NAME <b>Royal Carting Service</b>		2. TELEPHONE NUMBER	

H. TYPE OF OWNERSHIP

☐ 1. FEDERAL ☐ 2. STATE ☐ 3. COUNTY ☐ 4. MUNICIPAL ☒ 5. PRIVATE ☐ 6. UNKNOWN

I. SITE DESCRIPTION  
**Remote setting. No leachate.**

J. HOW IDENTIFIED (i.e., citizen's complaints, OSHA citations, etc.)	K. DATE IDENTIFIED (mo., day, & yr.)
--	--------------------------------------

L. PRINCIPAL STATE CONTACT 1. NAME <b>Jack Doty - NYS DEC White Plains</b>	2. TELEPHONE NUMBER <b>(914) 428-8927</b>
--	--

## II. PRELIMINARY ASSESSMENT (complete this section last)

A. APPARENT SERIOUSNESS OF PROBLEM <input type="checkbox"/> 1. HIGH <input checked="" type="checkbox"/> 2. MEDIUM <input type="checkbox"/> 3. LOW <input type="checkbox"/> 4. NONE <input type="checkbox"/> 5. UNKNOWN	
B. RECOMMENDATION <input type="checkbox"/> 1. NO ACTION NEEDED (no hazard) <input checked="" type="checkbox"/> 2. SITE INSPECTION NEEDED a. TENTATIVELY SCHEDULED FOR: b. WILL BE PERFORMED BY: <input type="checkbox"/> 3. IMMEDIATE SITE INSPECTION NEEDED a. TENTATIVELY SCHEDULED FOR: b. WILL BE PERFORMED BY: <input type="checkbox"/> 4. SITE INSPECTION NEEDED (low priority)	

C. PREPARER INFORMATION 1. NAME <b>M. Hauptman</b>	2. TELEPHONE NUMBER <b>(612) 264-1375</b>	3. DATE (mo., day, & yr.) <b>8-22-81</b>
--	--	---

## III. SITE INFORMATION

A. SITE STATUS <input type="checkbox"/> 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently.) <input type="checkbox"/> 2. INACTIVE (Those sites which no longer receive wastes.) <input checked="" type="checkbox"/> 3. OTHER (specify): <b>Those sites that include such incidents like "midnight dumping" where no regular or continuing use of the site for waste disposal has occurred.</b>	
B. IS GENERATOR ON SITE? <input type="checkbox"/> 1. NO <input type="checkbox"/> 2. YES (specify generator's four-digit SIC Code):	
C. AREA OF SITE (in acres) <b>5</b>	D. IF APPARENT SERIOUSNESS OF SITE IS HIGH, SPECIFY COORDINATES 1. LATITUDE (deg.-min.-sec.) 2. LONGITUDE (deg.-min.-sec.)
E. ARE THERE BUILDINGS ON THE SITE? <input type="checkbox"/> 1. NO <input type="checkbox"/> 2. YES (specify):	

## IV. CHARACTERIZATION OF SITE ACTIVITY

Indicate the major site activity(ies) and details relating to each activity by marking 'X' in the appropriate boxes.

A. TRANSPORTER		B. STORER		C. TREATER		D. DISPOSER	
1. RAIL	<input checked="" type="checkbox"/>	1. PILE	<input checked="" type="checkbox"/>	1. FILTRATION	<input checked="" type="checkbox"/>	1. LANDFILL	<input checked="" type="checkbox"/>
2. SHIP	<input type="checkbox"/>	2. SURFACE IMPOUNDMENT	<input type="checkbox"/>	2. INCINERATION	<input type="checkbox"/>	2. LANDFARM	<input type="checkbox"/>
3. BARGE	<input checked="" type="checkbox"/>	3. DRUMS	<input type="checkbox"/>	3. VOLUME REDUCTION	<input type="checkbox"/>	3. OPEN DUMP	<input type="checkbox"/>
4. TRUCK	<input type="checkbox"/>	4. TANK, ABOVE GROUND	<input type="checkbox"/>	4. RECYCLING/RECOVERY	<input type="checkbox"/>	4. SURFACE IMPOUNDMENT	<input type="checkbox"/>
5. PIPELINE	<input type="checkbox"/>	5. TANK, BELOW GROUND	<input type="checkbox"/>	5. CHEM./PHYS. TREATMENT	<input type="checkbox"/>	5. MIDNIGHT DUMPING	<input type="checkbox"/>
6. OTHER (specify):	<input type="checkbox"/>	6. OTHER (specify):	<input type="checkbox"/>	6. BIOLOGICAL TREATMENT	<input type="checkbox"/>	6. INCINERATION	<input type="checkbox"/>
				7. WASTE OIL REPROCESSING	<input type="checkbox"/>	7. UNDERGROUND INJECTION	<input type="checkbox"/>
				8. SOLVENT RECOVERY	<input type="checkbox"/>	8. OTHER (specify):	<input type="checkbox"/>
				9. OTHER (specify):	<input type="checkbox"/>		

## E. SPECIFY DETAILS OF SITE ACTIVITIES AS NEEDED

## V. WASTE RELATED INFORMATION

## A. WASTE TYPE

☐ 1. UNKNOWN    ☒ 2. LIQUID    ☐ 3. SOLID    ☒ 4. SLUDGE    ☐ 5. GAS

## B. WASTE CHARACTERISTICS

☒ 1. UNKNOWN    ☐ 2. CORROSIVE    ☐ 3. IGNITABLE    ☐ 4. RADIOACTIVE    ☐ 5. HIGHLY VOLATILE  
☐ 6. TOXIC    ☐ 7. REACTIVE    ☐ 8. INERT    ☐ 9. FLAMMABLE
☐ 10. OTHER (specify):

## C. WASTE CATEGORIES

1. Are records of wastes available? Specify items such as manifests, inventories, etc. below.

2. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which wastes are present.

a. SLUDGE	b. OIL	c. SOLVENTS	d. CHEMICALS	e. SOLIDS	f. OTHER
AMOUNT	AMOUNT	AMOUNT	AMOUNT	AMOUNT	AMOUNT
		300			
UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE
		55 gal drums			
(1) PAINT, PIGMENTS	<input checked="" type="checkbox"/> (1) OILY WASTES	<input checked="" type="checkbox"/> (1) HALOGENATED SOLVENTS	<input checked="" type="checkbox"/> (1) ACIDS	<input checked="" type="checkbox"/> (1) FLYASH	<input checked="" type="checkbox"/> (1) LABORATORY PHARMACEUT.
(2) METALS SLUDGES	(2) OTHER (specify):	(2) NON-HALOGENATED SOLVENTS	(2) PICKLING LIQUORS	(2) ASBESTOS	(2) HOSPITAL
(3) POTW		(3) OTHER (specify):	(3) CAUSTICS	(3) MILLING/MINE TAILINGS	(3) RADIOACTIVE
(4) ALUMINUM SLUDGE		unknown	(4) PESTICIDES	(4) FERROUS SMLTG. WASTES	(4) MUNICIPAL
(5) OTHER (specify):			(5) DYES/INKS	(5) NON-FERROUS SMLTG. WASTES	(5) OTHER (specify):
			(6) CYANIDE	(6) OTHER (specify):	
			(7) PHENOLS		
			(8) HALOGENS		
			(9) PCB		
			(10) METALS		
			(11) OTHER (specify):		

## V. WASTE RELATED INFORMATION (continued)

3. LIST SUBSTANCES OF GREATEST CONCERN WHICH MAY BE ON THE SITE (place in descending order of hazard).

4. ADDITIONAL COMMENTS OR NARRATIVE DESCRIPTION OF SITUATION KNOWN OR REPORTED TO EXIST AT THE SITE.

contains hundreds of 55 gallon drums  
from Texaco(?) and IBM(?)

## VI. HAZARD DESCRIPTION

A. TYPE OF HAZARD	B. POTENTIAL HAZARD (mark 'X')	C. ALLEGED INCIDENT (mark 'X')	D. DATE OF INCIDENT (mo., day, yr.)	E. REMARKS
1. NO HAZARD				
2. HUMAN HEALTH				
3. NON-WORKER INJURY/EXPOSURE				
4. WORKER INJURY				
5. CONTAMINATION OF WATER SUPPLY				
6. CONTAMINATION OF FOOD CHAIN				
7. CONTAMINATION OF GROUND WATER				
8. CONTAMINATION OF SURFACE WATER	X			Scout Creek
9. DAMAGE TO FLORA/FAUNA				
10. FISH KILL				
11. CONTAMINATION OF AIR				
12. NOTICEABLE ODORS				
13. CONTAMINATION OF SOIL				
14. PROPERTY DAMAGE				
15. FIRE OR EXPLOSION				
16. SPILLS/LEAKING CONTAINERS/ RUNOFF/STANDING LIQUIDS				
17. SEWER, STORM DRAIN PROBLEMS				
18. EROSION PROBLEMS				
19. INADEQUATE SECURITY				
20. INCOMPATIBLE WASTES				
21. MIDNIGHT DUMPING				
22. OTHER (specify):				

## VII. PERMIT INFORMATION

## A. INDICATE ALL APPLICABLE PERMITS HELD BY THE SITE.

- ☐ 1. NPDES PERMIT    ☐ 2. SPCC PLAN    ☐ 3. STATE PERMIT (specify): \_\_\_\_\_  
☐ 4. AIR PERMITS    ☐ 5. LOCAL PERMIT    ☐ 6. RCRA TRANSPORTER  
☐ 7. RCRA STORER    ☐ 8. RCRA TREATER    ☐ 9. RCRA DISPOSER

☒ 10. OTHER (specify): \_\_\_\_\_

## B. IN COMPLIANCE?

- ☐ 1. YES    ☐ 2. NO    ☒ 3. UNKNOWN

4. WITH RESPECT TO (list regulation name & number): \_\_\_\_\_

## VIII. PAST REGULATORY ACTIONS

- ☐ A. NONE    ☐ B. YES (summarize below)

## IX. INSPECTION ACTIVITY (past or on-going)

- ☐ A. NONE    ☒ B. YES (complete items 1, 2, 3, & 4 below)

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION
inspection	1-30-81	State	

## X. REMEDIAL ACTIVITY (past or on-going)

- ☐ A. NONE    ☐ B. YES (complete items 1, 2, 3, & 4 below)

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION

NOTE: Based on the information in Sections III through X, fill out the Preliminary Assessment (Section II) information on the first page of this form.

ce Helen log  
HQ

ORIG



POTENTIAL HAZARDOUS WASTE SITE IDENTIFICATION

REGION 2 SITE NUMBER NY 10125


NOTE: The initial identification of a potential site or incident should not be interpreted as a finding of illegal activity or confirmation that an actual health or environmental threat exists. All identified sites will be assessed under the EPA's Hazardous Waste Site Enforcement and Response System to determine if a hazardous waste problem actually exists.

A. SITE NAME ROYAL CARTING SERVICE		B. STREET (or other identifier) ROUTE 82 E. FISHKILL	
C. CITY EAST FISHKILL	D. STATE NY	E. ZIP CODE -	F. COUNTY NAME DUTCHESS
G. OWNER/OPERATOR (if known) 1. NAME SAMS		2. TELEPHONE NUMBER	
H. TYPE OF OWNERSHIP (if known) <input type="checkbox"/> 1. FEDERAL <input type="checkbox"/> 2. STATE <input type="checkbox"/> 3. COUNTY <input type="checkbox"/> 4. MUNICIPAL <input checked="" type="checkbox"/> 5. PRIVATE <input type="checkbox"/> 6. UNKNOWN			
I. SITE DESCRIPTION SACRO			
J. HOW IDENTIFIED (i.e., citizen's complaints, OSHA citations, etc.) UPDATE NYS LIST OF HAZARDOUS WASTE DISPOSITS		K. DATE IDENTIFIED (mo., day, & yr.) 04/14/80	
L. SUMMARY OF POTENTIAL OR KNOWN PROBLEM  100'S OF DRUMS, MANY FULL OF UNKNOWN CONTENTS			
M. PREPARER INFORMATION			
1. NAME ERNEST SCHMALZ		2. TELEPHONE NUMBER FTS 264-1573	3. DATE (mo., day, & yr.) 10-30-80



(USEPA, 1981)

POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT PART 1 - SITE INFORMATION AND ASSESSMENT				I. IDENTIFICATION	
<b>II. SITE NAME AND LOCATION</b>				01 STATE 02 SITE NUMBER NY 00001025	
01 SITE NAME (Legal, common, or descriptive name of site) Royal Carting Service		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Route 82			
03 CITY East Fishkill	04 STATE NY	05 ZIP CODE 12524	06 COUNTY Dutchess	07 COUNTY CODE 027	08 CONG DIST
09 COORDINATES LATITUDE		LONGITUDE			
10 DIRECTIONS TO SITE (Starting from nearest public road)					
<b>III. RESPONSIBLE PARTIES</b>					
01 OWNER (if known) Royal Carting Service		02 STREET (Business, mailing, residential) Route 82			
03 CITY East Fishkill	04 STATE NY	05 ZIP CODE	06 TELEPHONE NUMBER ( )		
07 OPERATOR (if known and different from owner)		08 STREET (Business, mailing, residential)			
09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER ( )		
13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: (Specify) <input type="checkbox"/> G. UNKNOWN					
14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply) <input type="checkbox"/> A. RCRA 3001 DATE RECEIVED: / / <input type="checkbox"/> B. UNCONTROLLED WASTE SITE (CERCLA 105 a) DATE RECEIVED: / / <input type="checkbox"/> C. NONE					
<b>IV. CHARACTERIZATION OF POTENTIAL HAZARD</b>					
01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE 1/30/80 <input type="checkbox"/> NO		BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input checked="" type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: (Specify) CONTRACTOR NAME(S):			
02 SITE STATUS (Check one) <input type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input checked="" type="checkbox"/> C. UNKNOWN		03 YEARS OF OPERATION BEGINNING YEAR ENDING YEAR UNKNOWN			
04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED I saw site with hundreds of 55 gallon drums from Texaco(?) and IBM(?). Remote setting, no leachate. Unknown chemicals.					
05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION					
<b>V. PRIORITY ASSESSMENT</b>					
01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents) <input type="checkbox"/> A. HIGH (Inspection required promptly) <input checked="" type="checkbox"/> B. MEDIUM (Inspection required) <input type="checkbox"/> C. LOW (Inspect on time available basis) <input type="checkbox"/> D. NONE (No further action needed, complete current disposition form)					
<b>VI. INFORMATION AVAILABLE FROM</b>					
01 CONTACT Jack Doty		02 OF (Agency/Organization) NYC DEC		03 TELEPHONE NUMBER 1212 468-1367	
04 PERSON RESPONSIBLE FOR ASSESSMENT M. Hampton		05 AGENCY USEPA		06 ORGANIZATION Hazardous Waste Unit	
		07 TELEPHONE NUMBER 1212 264-1575		08 DATE 6/28/81 MONTH DAY YEAR	



### IDENTIFICATION

01 STATE	02 SITE NUMBER
----------	----------------

## II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 WASTE STATES (Check all that apply)		02 WASTE QUANTITY AT SITE (Measure of waste quantities must be independent)	03 WASTE CHARACTERISTICS (Check all that apply)
<input type="checkbox"/> A. SOLID <input type="checkbox"/> B. POWDER, FINES <input checked="" type="checkbox"/> C. SLUDGE  <input type="checkbox"/> D. OTHER _____ (Specify)	<input checked="" type="checkbox"/> E. SLURRY <input type="checkbox"/> F. LIQUID <input type="checkbox"/> G. GAS	TONS _____  CUBIC YARDS _____  NO. OF DRUMS <u>300</u>	<input type="checkbox"/> A. TOXIC <input type="checkbox"/> B. CORROSIVE <input type="checkbox"/> C. RADIOACTIVE <input type="checkbox"/> D. PERSISTENT  <input type="checkbox"/> E. SOLUBLE <input type="checkbox"/> F. INFECTIOUS <input type="checkbox"/> G. FLAMMABLE <input type="checkbox"/> H. IGNITABLE  <input type="checkbox"/> I. HIGHLY VOLATILE <input type="checkbox"/> J. EXPLOSIVE <input type="checkbox"/> K. REACTIVE <input type="checkbox"/> L. INCOMPATIBLE <input type="checkbox"/> M. NOT APPLICABLE

### III. WASTE TYPE

WASTE TYPE				
CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE	300	DRUM	
OLW	OILY WASTE	300	DR	
SOL	SOLVENTS			
PST	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

#### IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

[illegible]

### V. FEEDSTOCKS (See Appendix for CAS Numbers)

V. FEEDSTOCKS (See Appendix for CAS Numbers)					
CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

**VI. SOURCES OF INFORMATION** (Cite specific references, e.g., state files, sample analysis, reports)

State files



POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NY

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

01 ☒ B. SURFACE WATER CONTAMINATION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

*Sprout Creek*

01 ☐ C. CONTAMINATION OF AIR

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

01 ☐ E. DIRECT CONTACT

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

01 ☐ F. CONTAMINATION OF SOIL

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 AREA POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

01 ☐ G. DRINKING WATER CONTAMINATION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

01 ☐ H. WORKER EXPOSURE/INJURY

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 WORKERS POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

01 ☐ I. POPULATION EXPOSURE/INJURY

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

APPENDIX C  
UPDATED NEW YORK STATE REGISTRY FORM

---

Name of Site: Royal Carting Service Region: 3  
County: Dutchess Town/City Hopewell Junction, & Fishkill  
Street Address Route 82, & Fishkill

From 1950 to 1962 hundreds of 35 and 55 gallon drums of non-hazardous waste chemicals from the Texaco Research Center were brought to the disposal site. These drums have since been removed but it is unknown what, if any additional wastes have been buried on the site.

Type of Site: Open Dump ☒ Treatment Pond(s) ☐ Number of Ponds \_\_\_\_\_  
Landfill ☐ Lagoon(s) ☐ Number of Lagoons \_\_\_\_\_  
Structure ☐

**Hazardous Wastes Disposed?**      **Confirmed** ☐      **Suspected** ☒

QUANTITY (Pounds, drums, tons,  
gallons)

Unknown.

C-1

